Att 1.

Christopher Hoare Tree Services Ltd

Limited Company No: 0466544
VAT Registration No: 750117661

Web Site: www.chtstrees.co.uk
Telephone: 02380 897933
Mobile: 0778 5522115

Exbury Estate Office
Exbury
Southampton
SO45 1AZ

Mr Alan McMutry
16 Lower St Helens Road
Hedge End
Southampton
Hampshire
SO30 0NB

Date Quote Sent: 11 March 2014

Quotation Information

Client ID No	3835
Quote No:	6579
Surveyor	Barry Folland
Site Ref No:	

Client: Mr Alan McMutry

Schedule Of Proposed Works

Site Address: 16 Lower St Helens Road, Hedge End, Southampton, Hampshire, SO30 0NB

Tree No	Tree Species	Description Of Work
T1	White poplar	Reduce height by 3 to 4 metres and reshape the long extending laterals by 5 metres. Remove all major deadwood
T2	Silver birch	Impinging on wall - fell to ground level and grind out residing stump. Replant with 1 x standard silver birch
T3	Plum	Leaning acutely towards the road - fell to ground level
T4	Beech Hedge	Located to the side of the drive - trim the front section to 6 - 7ft above ground level. Fell the 5 branches adjacent to the garage to ground level
T5	Purple leaved plum	Adjacent to pine - fell to ground level and grind out the residing stump
T6	Scots pine	Remove major deadwood throughout whole crown area (Deadwood > 25mm in diameter)
T7	Western red cedar	Reduce to 4 metres above ground level
T8	Lawson cypress	Fell to ground level and remove all arisings. Grind out residing sump
T9	Hazel coppice	Fell to ground level and remove all arisings. Grind out residing stump
G10	1 x Plum, 1 x Viburnum	Fell to ground level and remove all arisings. Grind out residing stumps
T11	Lawson cypress	Fell to ground level and remove all arisings
G12	Scots pine	Row of 6 Scots pines and 2 tall stumps. The pines are structurally poor due to the loss of apical dominance as a result of poor pruning / topping in the past which has lead to heavy side limbs.

Tree No	Tree Species	Description Of Work
		We recommed felling to ground level and replanting with 5 standard trees along this boundary.
		Felling of the trees
		Grind out Stumps 12-18inches below ground level
		Replanting
T13	Silver birch	Ivy clad and growing at an acute angle over the neighbours garden. Fell to ground level and grind out residing stump
T14	Purple leaved plum	A dead tree - fell to ground level and grind out residing stump

Total Value:

VAT: 20%

Total Inc VAT:

Scottish and Southern Energy
UK Power Networks