Christopher Hoare Tree Services Ltd

Limited Company No: 04766544
VAT Registration No: 750117661

Web Site: www.chtstrees.co.uk
Telephone: 02380 897933
Mobile: 0778 5522115

Exbury Estate Office
Exbury
Southampton
SO45 1AZ

Mr Chris Deacon
Royal Air Force Yacht Club
Riverside House Rope Walk
Hamble
Hampshire
SO31 4HD

Date Quote Sent: 05 September 2014

Quotation Information

Client ID No	4244
Quote No:	7383
Surveyor	Chris Hoare
Site Ref No:	

Client: Mr Chris Deacon

Schedule Of Proposed Works

Site Address: Riverside House Rope Walk, Hamble, Hampshire, SO31 4HD

Tree No	Tree Species	Description Of Work	Value £
T1	Macrocarpa	Crown clean removing major (>25mm dia) deadwood, broken & split branches Reduce back selected branches to provide 2.5 metres clearance from the moorings	
T2	Macrocarpa	Fell to ground level and remove all arisings	
T3	Macrocarpa	Remove all deadwood over 2" in diameter. Crown Lift to provide 5.2 metres clearance from ground level - over road and adjacent boat yard	
T4	Macrocarpa	Remove all deadwood over 2" in diameter. Crown Lift to provide 5.2 metres clearance from ground level - over road and adjacent boat yard	
T5	Macrocarpa	Fell to ground level and remove all arisings	
T6	Macrocarpa	Remove all deadwood over 2" in diameter. Crown Lift to provide 5.2 metres clearance from ground level - over road and adjacent boat yard Reduce back all overhanging branches that extend over The Royal Southern Sailing Club, by approimately 3 metres to suitable growth points	
T7	Macrocarpa	Remove all deadwood over 2" in diameter. Crown Lift to provide 5.2 metres clearance from ground level - over road and adjacent boat yard	
T8	Macrocarpa	Remove all deadwood over 2" in diameter. Crown Lift to provide 5.2 metres clearance from ground level - over road and adjacent boat yard	
T9	Macrocarpa	Fell to ground level and remove all arisings	

Tree No	Tree Species	Description Of Work	Value £
		Grind out Stump 12-18inches below ground level	

Total Value:

VAT: 20%

Total Inc VAT: