CLIENT NAME	CONTACT NUMBER	QUOTATION DATE	JOB NUMBER
Mrs Poole	02380 407737 staceypoole@btinternet.com	15/9/15	J15403

SITE ADDRESS	INSPECTED BY	Matt Godwin	
The Old Rectory School Lane Bursledon SO31 8BW	SITE PLAN ATTACHED		No
	COMMENCEMENT DATE	TBA	

JOB DESCRIPTION		
TREE NUMBER (price ex. VAT @20%)	SPECIES/ location	WORK REQUIRED
T1	Beech adj road.	Major root damage and advanced canker present on main stem leading to primary and secondary branch work. High potential of failure with high targets present. Major dead branches through crown. Sectional fell to just above ground level with the use of a MEWP and specialist rigging techniques. SSE will be informed as power lines will require shut down.
Stump G1	Beech stump and Rhododendron stump.	Grind to approx. 300mm below ground level.
G1	Conifer Hedge on north eastern boundary.	Sectional fell to just above ground level with the use of a MEWP and rigging techniques. Grind stumps to approx. 300mm below ground level. All timber to be retained on site....

A site specific risk assessment will be undertaken before the commencement of works, this will encompass site hazards and environmental considerations.

Where required, and unless otherwise mentioned:

- Works will be undertaken using rigging/lowering techniques to prevent damage to the surrounding features.
- Traffic and pedestrian management incorporating stop/go boards to protect the public will be used.