CLIENT NAME	CONTACT NUMBER	QUOTATION DATE	JOB NUMBER
Mr Flynn	02380 404382 .f.flynn@btinternet.com	24/11/14	J14675

SITE ADDRESS	INSPECTED BY	Matt Godwin	
4 Ashley Court Bursledon, SO31 8AT	SITE PLAN ATTACHED		No
	COMMENCEMENT DATE	TBA	

JOB DESCRIPTION		
TREE NUMBER (price ex. VAT @20%)	SPECIES/ location	WORK REQUIRED
T1	Pine adj drive – leaning towards No. 1.	Crown lift to 6m all round with emphasis on lateral branches encroaching No 1. Creating an upswept canopy. Live pruning wounds kept to a max of 100mm. Shorten Southern primary stem by 3m from tips to suitable growth points due to over extension and excessive leverage towards dwelling within a tight v shape union.

A site specific risk assessment will be undertaken before the commencement of works, this will encompass site hazards and environmental considerations.

Where required, and unless otherwise mentioned:

- Works will be undertaken using rigging/lowering techniques to prevent damage to the surrounding features.
- Traffic and pedestrian management incorporating stop/go boards to protect the public will be used.
- All brushwood will be chipped and removed from site for recycling. All timber will be removed from site for recycling.

A Guide to the terminology used in your quotation

Titchfield Tree Services, 18 Little Park Farm Road, Segensworth West, Fareham, PO15 5TD
matt@titchfieldtreeservices.com