OMEGA STRUCTURES
29 Kingsclere Drive
Bishops Cleeve
Cheltenham GL52 8TG
Tel. +44 (0)121 288 5440
Fax +44 (0)121 275 6043
info@omegastructures.com

Mr G Mattey
Prysmian Cables & Systems Limited
Chickenhall Lane
Eastleigh
SO50 6YU

25 November 2014

Order Acknowledgement

Dear Mr Mattey

Thank you very much for your recent order ref. **4500362263** which we are now happy to acknowledge, subject to the terms and conditions detailed below:

Position 1.0

Quantity Description

---

1 ALUFLEX Industrial marquee

Width:	15.00 metres
Length:	30.00 metres
Bay size:	2.50 metres
Eaves height:	5.00 metres
Ridge height:	7.01 metres
Snow loading:	20 kg per square metre
Framework:	Non-Anodised aluminium with galvanised steel connection pieces. The design and manufacture complies with currently applicable DIN EN 13782 standards for temporary structures.
Anchoring:	With mechanical bolts on concrete base (slab or plinth)
Covers:	PVC coated polyester fabric, 650 gr. / sqm, flame retardant to BS 5438, white translucent roof covers and gable triangles.

Double skin:	12 No. Anti-condensation double skin roof section.
Walls:	Profiled single skin steel cladding, horizontally fitted, 0.63mm thickness, standard colour RAL9002 (grey white).
Access:	2 No. Electrical roller shutter door 3.83m width x 4.0m height in one long side (connection to mains to be carried out by certified elcetricians) 2 No. Single steel personnel access door 1 x 2.125 m in side
100 lux lighting:	12 No. IP 54 Osram Dulux EL 2x55W low consumption lights aluminium casing, macrolon front cover and interconnecting wiring (connection to mains to be carrid out by certified electricians).

Total purchase cost ex-works: £43,500.00

Position 2.0

Installation costs:

Complete installation including ancillary costs for possible tool hire and travel costs of our erection crew. Please note plant hire costs are included.

Total : £7,500.00 + VAT.

Transportation cost :

Total : included above

A calculation note delivered by the German TÜV certification body, together with layout and elevation drawings can be supplied on demand at any point in time.

The following options are NOT included:

- Insulated roof and wall sections,
- Guttering with downpipes (subject to onsite drainage),
- Industrial flooring allowing heavy vehicle traffic,
- Peripheral ground seal (subject to onsite ground conditions)
- Emergency exit lighting.

Prerequisites for implementation :

- A stable, level and even surface and a clear site with sufficient peripheral clear space are required, together with a sufficiently compact ground for anchoring by 1-metre long steel stakes or rawl bolts
- The site should be clear of any underground services (cables, pipes, etc.) or their precise location clearly identified.
- Free access must be provided for an articulated lorry to be unloaded on site.
- A telehandler and an access platform should be made available, unless otherwise stated.
- Possible late costs incurred because of the planning process, deliverance of planning permission, calculation note, etc. are born by the client.
- Implementation prerequisites as well as technical drawings are part of the order.
- A detailed specification of the proposed product is available on request.

Scheduled delivery date:	To be confirmed – subject to planning permission (earliest possible week commencing 12 January 2015)
Means of delivery:	By transport company (articulated lorry)
Delivery address:	Plant 11, Special cables, Prysmian Cables & Systems, Chickenhall Lane, Bishopstoke, Eastleigh SO50 6YU
Scheduled start of installation:	To be confirmed
Terms of payment:	100% upon installation completion, End of month of invoice date + 1 month + 6 days

Please sign and return this acknowledgement as acceptance of the details and conditions as set forth above.

Signed for **Prysmian Cables & Systems Limited**…….. ….Date……