NOTES:

1. This drawing is to be read in conjunction with all relevant contract drawings and specifications with any conflicting information to be brought to the attention of Deacon Design before works commence on site.

2. Do not scale from this drawing, always work to noted dimensions.

3. All given dimensions in mm.

0 5 10 15 20 25m

1 : 250

KEY

- Application site boundary
- Existing trees / hedgerows on site, retained
- Existing grassland retained and enhanced with tussocky grassland mixture, *Emorsgate's EM10 Tussock mixture (5% of the area seeded) or similar and approved*
- Existing grassland retained - managed grassland, used as Public Open Space, area of informal recreation
- Existing vegetation removed (shrubs, bramble)
- Proposed ornamental tree planting
- Proposed ornamental shrub planting
- Proposed woodland understorey planting
- Proposed tree and shrub mix planting to M27 buffer
- Proposed shade tolerant meadow seeding, *Emorsgate's EW1 Woodland Mixture or similar and approved*
- Proposed Swale seed mix, Emorsgate EM8 - Meadow mixture for wetlands *or similar and approved*
- Proposed marginal plug planting
- Proposed lawn areas to private gardens
- Proposed flowering lawn to road verges
- Proposed bulb planting within grassland

NOTE: For Full Planting Schedule, see drawing No. DD111.L03

LOCATION PLAN - Not to scale



FINAL

DATE	DRAWN	DESCRIPTION OF REVISION	REVISION LETTER	CHECKED BY
09.09.16	PD	Updated Layout	B	PD
01.09.16	PD	Updated Layout	A	PD

DRAWING STATUS

FOR PLANNING

DEACON DESIGN
Landscape Architecture | Masterplanning | Urban Design
Furzehall Farm, Wickham Road, Fareham PO16 7JH
Tel: 01329 312 045 Email: info@deacondesign.co.uk

Copyright Deacon Design 2016

PROJECT TITLE :

Land at Providence Hill, Bursledon

Foreman Homes Group

PROJECT NUMBER :	PLOT DATE :
DD111	23.05.16
DRAWING SCALE : 1:250	APPROVED BY : -
PAPER SIZE : A1	DRAWN BY : PD

DRAWING TITLE :

Detailed Planting Plan 1 of 3

-

-

DRAWING NUMBER :	REVISION LETTER :
D111.L02	B

DRAWING FILE LOCATION :

C:\Users\Suzi\Desktop\Dropbox (Deacon Design Ltd)\03 DD PROJECTS\DD111 Providence Hill\Revised Scheme\04-Drawings\Autocad\L-Landscape Dwgs\DD111L02-04_Detailed Planting Plan.dwg

Woodland buffer to SINC edge
native saplings planted to 5% of the area
9No Betula pubescens
9No Crataegus monogyna
9No Corylus avellana
9No Quercus robur
9No Salix cinerea

Sub Station

POS

PLOT 30 PLOT 29 PLOT 28 PLOT 27 PLOT 26 PLOT 25 PLOT 24 PLOT 23 PLOT 22 PLOT 21 PLOT 20 PLOT 19 PLOT 18 PLOT 17 PLOT 16 PLOT 15 PLOT 14 PLOT 13 PLOT 12 PLOT 11 PLOT 10 PLOT 9 PLOT 8 PLOT 7 PLOT 6 PLOT 5 PLOT 4 PLOT 3 PLOT 2 PLOT 1

Meadow Vale

Cloverhayes

Wickham Road

Existing grassland retained and enhanced with plug planting on 5 % of the area:
Carex hirta
Carex nigra
Juncus inflexus
Lychnis flos-cuculi
Pulicaria dysenterica

Marginal plug planting to stream edge
(25% of the area planted with plug plants)
Potamogeton crispus
Butomus umbellatus
Myosotis scorpioides
Myriophyllum spicatum
Mentha aquatica
Alisma plantago-aquatica

Native shrub planting, 10% of the area planted
9No Ilex aquifolium
9No Corylus avellana
9No Crataegus monogyna
4No Prunus spinosa
4No Viburnum opulus
19No Hedera helix

Understorey enhancements, 10% of the area planted:
2No Ilex aquifolium
2No Viburnum opulus
5No Hedera helix
3No Luzula sylvatica
6No Anemone nemorosa
6No Hyacinthoides non-scripta
6No Dryopteris affinis 'Crispa'
6No Primula vulgaris

Understorey enhancements, 10% of the area planted
11No Ilex aquifolium
11No Viburnum opulus
22No Hedera helix
16No Luzula sylvatica
27No Anemone nemorosa
27No Hyacinthoides non-scripta
27No Dryopteris affinis 'Crispa'
27No Primula vulgaris

Understorey enhancements, 10% of the area planted
5No Ilex aquifolium
5No Viburnum opulus
10No Hedera helix
7No Luzula sylvatica
13No Anemone nemorosa
13No Hyacinthoides non-scripta
13No Dryopteris affinis 'Crispa'
13No Primula vulgaris

Proposed bulb planting

Proposed bulb planting

Proposed bulb planting

Hedgerow enhancement
6No Ilex aquifolium
20No Corylus avellana
13No Crataegus monogyna
13No Prunus spinosa
13No Viburnum opulus

Hedgerow enhancement
11No Ilex aquifolium
35No Corylus avellana
23No Crataegus monogyna
23No Prunus spinosa
23No Viburnum opulus

Hedgerow enhancement
1No Ilex aquifolium
5No Corylus avellana
3No Crataegus monogyna
3No Prunus spinosa
3No Viburnum opulus

Hedgerow enhancement
5No Ilex aquifolium
17No Corylus avellana
11No Crataegus monogyna
11No Prunus spinosa
11No Viburnum opulus

Hedgerow enhancement
1No Ilex aquifolium
4No Corylus avellana
2No Crataegus monogyna
2No Prunus spinosa
2No Viburnum opulus

1No Acer campestre 'Streetwise'
1No Quercus robur
3No Betula pendula
3No Salix fragilis
2No Salix fragilis
3No Alnus glutinosa
1No Prunus avium
1No Prunus avium 'Plena'
1No Carpinus betulus 'Fastigiata'
1No Salix purpurea 'Nana'
1No Pear 'Concorde'
3No Apple 'Cox'
1No Apple 'Cox'
1No Corylus maxima 'Purpurea'
1No Malus 'Evereste'
1No Pear 'Concorde'
1No Hydrangea petiolaris
1No Acer campestre 'Streetwise'
1No Quercus robur
1No Quercus robur
1No Quercus robur