Planting Schedule

Trees

Species Name	Girth	Height	Density	Specification	No.
Carpinus betulus		100-125cm	0.5Clr Double Staggered at 0.4m offset	BR	512 -
Amelanchier lamarckii	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem 175-200 :RB: Native	1 -
Pyrus calleryana 'Chanticleer'	14-16cm	425-600cm	Counted	Extra Heavy Standard :Clear Stem min. 200 :RB: Native	1 -
Tilia cordata	14-16cm	425-600cm	Counted	Extra Heavy Standard :Clear Stem min. 200 :RB: Native	2 -
Apple 'Bramley'	14-16cm	450-500cm	Counted	2-5yr: M26	2 -

Shrubs

Species Name	Height	Pot Size	Specification	Density	No.
Camellia 'Constance'	80-100cm	10L	Branched :6/9 brks :C	Counted	2 -
Cornus alba 'Sibirica'	60-80cm	5L	Bushy	4/m²	7 -
Escallonia 'Apple Blossom'	30-40cm	3L	Bushy	5/m²	12 -
Euonymus fortunei 'Emerald Gaiety'	20-30cm	3L	Bushy	4/m²	13 -
Hamamelis intermedia 'Pallida'	100-150cm	15L	Branched	Counted	1 -
Hypericum 'Hidcote'	30-40cm	3L	Bushy	4/m²	11 -
Lonicera 'Loughall Green'	40-60cm	3L	Bushy	4/m²	18 -
Mahonia aquifolium 'Apollo'	40-60cm	5-7.5L	Leader With Laterals	3/m²	13 -
Philadelphus 'Manteau d'Hermine'	40-60cm	3L	Bushy	3/m²	6 -
Pittosporum tenuifol. 'Irene Patterson'	30-40cm	3L	Bushy	4/m²	7 -
Pittosporum tenuifolium 'Golf Ball'	30-40cm	3L	Bushy	4/m²	14 -
Rosa 'Ballerina'	40-60cm	3L	Bushy	4/m²	7 -
Salvia officinalis 'Berggarten'	30-40cm	3L	Bushy	4/m²	29 -
Sarcococca hookerana digy. 'Purple Stem'	30-40cm	3L	Bushy	4/m²	24 -
Skimmia japonica reevesiana	30-40cm	3L	Bushy	4/m²	21 -
Sorbus aria	400-450cm		Heavy Standard :Clear Stem min. 200 :C: Native	Counted	1 -
Tilia cordata	400-450cm		Heavy Standard :Clear Stem min. 200 :C: Native	Counted	1 -
Viburnum opulus 'Compactum'	40-60cm	3L	Bushy	4/m²	6 -
Viburnum tinus	40-60cm	5L	Bushy	0.5Clr Double Staggered at 0.4m offset	119 -
Viburnum tinus	30-40cm	3L	Bushy	3/m²	8 -

SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTES:
DO NOT SCALE FROM DRAWING
NOT FOR CONSTRUCTION, FOR PLANNING PURPOSES ONLY

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on sheet
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties.
- Proposed *Carpinus* (hornbeam) hedge planting to be planted in a double staggered row 300mm apart and at 400mm centres in each row. To be maintained at 1m height
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Existing grass to be retained. Any bare patches to receive good quality amenity grass turves laid in line with good horticultural practices
- Proposed wildflower grassland areas, to be seeded with WFG18 'Butterfly and Honeybee' seed mix as supplied by Germinal Seeds and sown at 5 grams per msq, or similar and approved.
- Proposed Mown Grass Path, where bare patches are to be seeded with EM2 Mixture as supplied by Emorsgate and sown at 4 grams per msq, or similar and approved
- Priora permeable paving in brindle laid in herringbone pattern with contrast colour blocks to demarcate parking spaces. Laid in line with engineer's details.
- Grass grid reinforcement to be honeycomb from COREgravel or similar
- Saxon concrete paving slabs 450x450mm in buff laid in stack bond from Marshalls or similar and approved. Laid in line with engineer's details.
- Proposed private footpaths to house Fairstone Setts Autumn Bronze mixed sizes from Marshalls or similar and approved. Laid to engineer's details.

Rev	Date	Details	Drawn

ACD ENVIRONMENTAL

HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

4 & 5 The Old Mill, Fry's Yard, Bridge Street,
Godalming, GU7 1HP
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close,
Eastleigh, SO50 9SX
Tel: 02382 026300


email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

EASTLEIGH BOROUGH COUNCIL

scheme: Victoria House
Horton Heath
client: Eastleigh Borough Council
drawing: Landscape Proposals
date: July 2022
scale: 1:200@A1
drawing no: EB22850 11
drawn: LS checked: DKM

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.

Tree Pit Detail: Soft Landscape



Components as supplied from GreenBlue Urban or similar