

RMJ SURVEYS TOPOGRAPHIC LEGEND

TOPOGRAPHIC ABBREVIATIONS	
ACU	AIR CONDITIONING UNIT
AV	AIR VALVE
B	BOLLARD
BB	BELISHA BEACON
BIN	LITTER BIN
BLT	BASEMENT LIGHT
BS	BUS STOP
BTMH	TELECOM MANHOLE
C/COL	COLUMN
CB	CONTROL BOX
CH	COAL HOLE
CL	COVER LEVEL
CRW	CONCRETE RETAINING WALL
CTV	CABLE TELEVISION PIT
DK	DROP KERB
ECB	ELECTRICITY CONTROL BOX
ELCP	ELECTRICITY CABLE PIT
EP	ELECTRICITY POLE
ER	EARTHING ROD
FB	FLOWER BED
FH	FIRE HYDRANT
FS	FLAG STAFF
FWMH	FOUL WATER MANHOLE
G	GULLY
GV	GAS VALVE
HT	HEIGHT
IC	INSPECTION COVER
KO	KERB OUTLET
LB	LETTER (POST) BOX
LP	LAMP POST
MH	MANHOLE
MKR	MARKER POST
MS	MILE STONE
NB	NOTICE BOARD
NP	NAME PLATE
P	POST
PM	PARKING METER
RE	RODDING EYE
RP	REFLECTOR POST
RS	ROAD SIGN
RTW	RETAINING WALL
RWP	RAIN WATER PIPE
SC	STOP COCK
SLM	SLOPING MASONARY
SRW	STONE RETAINING WALL
STAY	STAY WIRE
SV	STOP VALVE
SWMH	STORM WATER MANHOLE
TCB	TELEPHONE CALL BOX
TAP	STAND PIPE
TP	TELEGRAPH POLE
TL	TRAFFIC LIGHT
TM	TICKET MACHINE
△	SURVEY STATION
UTL	UNABLE TO LIFT
VP	VENT PIPE
WIC	WATER CO. INSPECTION COVER
WM	WATER METER
WO	WASH OUT
WT	WATER TROUGH

SURFACE ABBREVIATIONS	
BP	BLOCK PAVED
B/S	BRICK SETTS
CPS	CONCRETE PAVING SLABS
FB	FLOWER BED
FP	FOOTPATH
SPS	STONE PAVING SLABS
TMC	TARMAC
TPS	TACTILE PAVING SLABS

FENCE ABBREVIATIONS	
BWF	BARBED WIRE FENCE
CBF	CLOSED BOARD FENCE
CBR	CRASH BARRIER
CIF	CORRUGATED IRON FENCE
CPF	CHESTNUT PALING FENCE
IRF	IRON RAILING FENCE
IWF	INTERWOVEN FENCE
LLF	LARCH LAP FENCE
Mis.F	MISCELLANEOUS FENCE
OBF	OPEN BOARD FENCE
PCF	POST AND CHAIN FENCE
PIF	PICKET FENCE
PRF	POST AND RAIL FENCE
PWF	POST AND WIRE FENCE
TLS	TRELLIS
WMF	WIRE MESH FENCE

LEVEL ABBREVIATIONS	
+1.23	SPOT LEVEL (+ INDICATES POS.)
BL	BED LEVEL
BTL	BASEMENT LEVEL
CL	COVER LEVEL
EL	EAVE LEVEL
FL	FLOOR LEVEL
IL	INVERT LEVEL
RL	RIDGE LEVEL
RFL	ROOF LEVEL
SL	SUMP LEVEL
SFL	SOFFET LEVEL
SPL	SPRING LEVEL
THL	THRESHOLD LEVEL
WL	WATER LEVEL

TREE ABBREVIATIONS	
ALD	ALDER
BCH	BEECH
CHY	CHERRY
CYP	CYPRESS
DEC	DECIDUOUS
EGN	EVERGREEN
HAW	HAWTHORN
HC	HORSE CHESTNUT
HOL	HOLLY
LPN	LONDON PLANE
POP	POPLAR
RHD	RHODODENDRON
RWN	ROWAN
SB	SILVER BIRCH
SCN	SWEET CHESTNUT
WLW	WILLOW
WNT	WALNUT

RMJ SURVEYS DRAWING KEY

BUILDING
GLASS ROOFED BUILDING
BANKING
GATE
0.22 Wall Ht 1.80 — WALL
RTW — RETAINING WALLS
Hedge Ht 2.50 — VEGETATION
OSBM 50.000m / TBM 50.000m — ORDINANCE SURVEY OR TEMPORARY BENCHMARKS
Species Bole/Spread/Ht — TREES

DRAWING REVISIONS

NUMBER	DATE	DESCRIPTION	BY

This drawing has been produced for the client set out in the title, to an agreed specification, and hence defines the limitations of RMJ Surveys LTD's Liability.

Underground services cannot be guaranteed, and users of this information should satisfy themselves of drainage details (type, size and route) before commencement of work. RMJ Services LTD cannot be held responsible for hidden or obscured services at the time of survey.

Tree species and sizes on this drawing are not guaranteed, and if critical should be verified by an arboriculturist. Tree spreads are average about the bole, and heights are approximate at the time of the survey.

CO-ORDINATE SCHEDULE

STN	EASTING	NORTHING	ELEVATION	DESCRIPTION
1	500.000	1000.000	48.815	MAG NAIL
2	488.506	1000.546	48.648	MAG NAIL
3	493.291	1022.260	49.290	TEMP PEG
4	506.532	1023.642	49.472	TEMP PEG
5	510.096	1038.444	49.898	TEMP NAIL
6	504.796	1049.177	50.389	TEMP PEG

NORTH APPROXIMATE

RMJ Surveys Ltd.

• Topographical Site Surveys • Measured Building Surveys •
• Site Engineering • Boundary Plans • CAD •

Registered Company Address:
"Surveys House"
15 Cheriton Rd
Fulflood
Winchester
Hampshire SO22 5EQ.

Phone: 01962 680 275
Site/Mobile: 07809 740 524
Email: mail@rmj-surveys.co.uk
Web: www.rmj-surveys.com

PROJECT TITLE.	6 GROSVENOR ROAD, HILTINGBURY, CHANDLERS FORD, SOUTHAMPTON, HAMPSHIRE, SO53 5BW.
DRAWING TITLE.	TOPOGRAPHICAL SURVEY.
LEVEL DESCRIPTION.	LEVELS BASED ON TBM, VALUE: 50.000m SITAUED DPC LEVEL, NUMBER 6. (SHOWN).
CLIENT.	MR SURJIT DHALIWAL.
DRAWING NUMBER.	220214_J6608_TOPO.
DRAWING SCALE.	1 : 100 SCALE.
SHEET SIZE.	A0 SHEET X1.
DRAWN BY.	RJ.
DRAWING DATE.	FEBRUARY 2022.