

T2 - Beech sp. to reduce the western crown by 1.5m away from the property, stem diameter cuts no greater than 35mm. Crown lift lower tertiary foliage 4m from ground level, with stem diameter cuts no greater than 25mm.

T3 - Sycamore sp. to reduce the western crown 1.5m away from the property, stem diameter cuts no greater than 35mm . Crown lift lower tertiary foliage 4m from ground level , with diameter cuts no greater than 25mm.

T4 - Sycamore sp. Crown lift lower tertiary foliage 4m from ground level, stem diameter cuts no greater than 25mm.

T5 - Sycamore sp. Crown lift lower tertiary foliage 4m from ground level, stem diameter cuts no greater than 25mm.



Diagrams are approximate for example purposes only and do not represent the finished shape; the pruning points will be taken back to the nearest best practice pruning in accordance with BS3998(2010)