

GENERAL NOTES

1. THIS DRAWING IS TO BE READ TOGETHER WITH ALL OTHER RELEVANT DRAWINGS AND SPECIFICATION
2. DO NOT SCALE THIS DRAWING. USE FIGURED DIMENSIONS ONLY. IF IN DOUBT ASK.
3. FOR TYPICAL DETAILS REFER TO DRAWINGS 070009-159 - 070009-167.
4. FOR TENDER PURPOSES FOUNDATIONS WIDTHS ARE; 450mm EXT, 450mm INT & 600mm PARTY UNLESS DIMENSIONED OTHERWISE.
- 5.a) FOUNDATIONS WILL BE MINIMUM 400mm THICK. IF NOTED OTHERWISE, CONFIRM BEFORE CONSTRUCTION.
b)TOP OF FOUNDATION STATED IS A MAXIMUM, ACTUAL VALUE MAY VARY DUE TO SITE LEVELS.
c)TOP OF FOUNDATION TO BE LOWER THAN 200mm BELOW EXISTING GROUND LEVEL, WHERE NECESSARY STEP TO ACCOMMODATE EGL IN ACCORDANCE WITH BUILDING REGS PART A.
6. ABBREVIATIONS
FFL - FINISHED FLOOR LEVEL SSL - STRUCTURAL SLAB LEVEL
TOF - TOP OF FOUNDATION BOF - BOTTOM OF FOUNDATION
UNO - UNLESS OTHERWISE NOTED TBC - TO BE CONFIRMED
7. ENSURE THE FOUNDATION BASE IS FOUNDED ON COMPETENT BEARING STRATA. FOR SITE SPECIFIC GROUND BEARING CAPACITIES, REFER TO SITE INVESTIGATION. REMOVE ANY HARD / SOFT SPOTS ENCOUNTERED AND REPLACE WITH A TYPE 1 WELL COMPACTED GRANULAR MATERIAL.

Pile No.	Plot No.	Easting	Northing	Load (kN)	Cut Off (m)
152	333-335	451206957	114533805	131	18.075
153	333-335	451209667	114533770	163	18.075
154	333-335	451212378	114533735	219	18.075
155	333-335	451215929	114533690	165	18.075
156	333-335	451206989	114536305	132	18.075
157	333-335	451212410	114536235	99	18.075
158	333-335	451215961	114536190	166	18.075
159	333-335	451207021	114538805	238	18.075
160	333-335	451209731	114538770	239	18.075
161	333-335	451212442	114538735	255	18.075
162	333-335	451215993	114538690	199	18.075
163	333-335	451207053	114541304	115	18.075
164	333-335	451212474	114541235	86	18.075
165	333-335	451216025	114541189	149	18.075
166	333-335	451207085	114543804	236	18.075
167	333-335	451210339	114543762	224	18.075
168	333-335	451212506	114543735	290	18.075
169	333-335	451216057	114543689	255	18.075
170	333-335	451207121	114546636	170	18.075
171	333-335	451210376	114546595	139	18.075
172	333-335	451212542	114546567	136	18.075
173	333-335	451216093	114546521	154	18.075
174	333-335	451207158	114549469	122	18.075
175	333-335	451210412	114549427	148	18.075
176	333-335	451212579	114549399	158	18.075
177	333-335	451216130	114549354	123	18.075
178	327/328	451258626	114535409	165	18.375
179	327/328	451261126	114535377	167	18.375
180	327/328	451263626	114535345	189	18.375
181	327/328	451266458	114535309	155	18.375
182	327/328	451269291	114535273	123	18.375
183	327/328	451258672	114538960	223	18.375
184	327/328	451261172	114538928	96	18.375
185	327/328	451263672	114538896	226	18.375
186	327/328	451266504	114538860	136	18.375
187	327/328	451269336	114538824	158	18.375
188	327/328	451258707	114541671	163	18.375
189	327/328	451263699	114541063	224	18.375
190	327/328	451266532	114541026	139	18.375
191	327/328	451269364	114540990	148	18.375
192	327/328	451258742	114544381	128	18.375
193	327/328	451261241	114544349	130	18.375
194	327/328	451263741	114544317	233	18.375
195	327/328	451266573	114544281	171	18.375
196	327/328	451269406	114544244	122	18.375
197	355/356	451289790	114534287	117	17.425
198	355/356	451292726	114534142	155	17.425
199	355/356	451295661	114533997	235	17.425
200	355/356	451298596	114533851	204	17.425
201	355/356	451301531	114533706	156	17.425
202	355/356	451289948	114537468	166	17.425
203	355/356	451292883	114537323	161	17.425
204	355/356	451295830	114537402	198	17.425
205	355/356	451298058	114537442	179	17.425
206	355/356	451301707	114537261	213	17.425
207	355/356	451290088	114540297	188	17.425
208	355/356	451293023	114540152	159	17.425
209	355/356	451295959	114540007	197	17.425
210	355/356	451298216	114540622	130	17.425
211	355/356	451301865	114540441	153	17.425
212	355/356	451290265	114543866	138	17.425
213	355/356	451292096	114544451	55	17.425
214	355/356	451293144	114543723	96	17.425
215	355/356	451294259	114544344	55	17.425
216	355/356	451296135	114543575	189	17.425
217	355/356	451298373	114543802	197	17.425
218	355/356	451302022	114543621	155	17.425
*Pile Cutoff Level refers to concrete level only. Ensure pile reinforcement remains long enough to lap with groundbeam reinforcement. To piling contractors details.					

-	-	-	-		-
-	-	-	-		-
CO	25/01/19	CO	CW		FIRST ISSUE
Rev	Date	By	Chkd		Description

Status: FOR CONSTRUCTION

Client:



Project: BOORLEY GREEN C5 & C6
WINCHESTER ROAD
HAMPSHIRE

Drawing:PILE COORDINATE SCHEDULE
SHEET 1 OF 1