

Planting Schedule

Trees	Species Name	Girth	Height	Density	Specification	No.
	Carpinus betulus		200-250cm	0.5Citr	Double Staggered at 0.4m offset	Feathered 2x RB 619
	Sorbus aucuparia	12-14cm	300-350cm	Counted	Selected Standard Clear Stem min. 200 : 4 brks 2x RB	5
	Malus floribunda	12-14cm	300-350cm	Counted	Selected Standard Clear Stem min. 200 : 4 brks 2x RB	5
	Prunus avium	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem min. 200 : 5 brks 3x RB	2
	Sorbus aria 'Majestica'	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem min. 200 : 5 brks 3x RB	1
	Acer campestre	18-20cm	450-500cm	Counted	Extra Heavy Standard Clear Stem min. 200 RB	20
	Carpinus betulus	18-20cm	450-500cm	Counted	Extra Heavy Standard Clear Stem min. 200 RB	6
	Acer campestre 'Elsrijk'	18-20cm	450-500cm	Counted	Extra Heavy Standard Clear Stem min. 200 RB	1
	Betula pendula	18-20cm	450-500cm	Counted	Extra Heavy Standard Clear Stem min. 200 RB	13
	Quercus robur	20-25cm	500-600cm	Counted	Semi-Mature Clear Stem min. 200 : 3x/4x RB	18
	Corylus colurna	20-25cm	500-600cm	Counted	Semi-Mature Clear Stem min. 200 : 3x/4x RB	1

Shrubs

Species Name	Height	Pot Size	Specification	Density	No.
Cornus sanguinea	30-40cm	5-7.5L	Bushy C	0.5Citr	89
Euonymus fortunei 'Dart's Blanket'	30-40cm	3L	Bushy 5 brks C	4/m ²	35
Hebe albicans 'Red Edge'	30-40cm	3L	Bushy C	0.5Citr	86
Skimmia confusa 'Kew Green'	30-40cm	3L	Bushy C	0.5Citr	54
Viburnum opulus	60-80cm	5-7.5L	Bushy C	0.5Citr	81
Viburnum tinus	40-60cm	5-7.5L	Bushy C	0.5Citr	49

Herbaceous

Species Name	Pot Size	Specification	Density	No.
Deschampsia cespitosa	3L	Full Pot	0.5Citr	30
Geranium renardii 'Brookside'	3L	Full Pot	0.5Citr	62
Persicaria affinis 'Darjeeling Red'	5-7.5L	Full Pot	0.5Citr	52
Sedum spectabile 'Brilliant'	5-7.5L	Full Pot	0.5Citr	8
Stipa tenuissima	3L	Full Pot	0.5Citr	53
Verbena bonariensis	5-7.5L	Full Pot	0.5Citr	23

Native Scrub Planting

Number	Species	Specification	Density	Percentage Contribution
472 -	Corylus avellana	1+2 or 1/2 Branched 3 brks B	2/m ²	35%
201 -	Ilex aquifolium	Bushy 3 brks C	2/m ²	15%
65 -	Lonicera periclymenum	3 brks Several shoots C	2/m ²	5%
201 -	Sambucus nigra	1+1 or 1/1 Branched 3 brks B	2/m ²	15%
404 -	Viburnum opulus	1+2 or 1/2 Branched 3 brks B	2/m ²	30%
Total :1343 -				

Native Hedgerow Mix

Number	Species	Specification	Density	Percentage Contribution
181 -	Acer campestre	Standard B	0.4Citr Double Staggered at 0.3m offset	15%
181 -	Carpinus betulus	Transplant	0.4Citr Double Staggered at 0.3m offset	15%
181 -	Crataegus monogyna	Transplant	0.4Citr Double Staggered at 0.3m offset	15%
58 -	Lonicera periclymenum	Several Shoots	0.4Citr Double Staggered at 0.3m offset	5%
120 -	Prunus avium	Feather	0.4Citr Double Staggered at 0.3m offset	10%
181 -	Prunus spinosa	Branched	0.4Citr Double Staggered at 0.3m offset	15%
58 -	Rosa canina	Branched	0.4Citr Double Staggered at 0.3m offset	5%
120 -	Sambucus nigra	Bushy	0.4Citr Double Staggered at 0.3m offset	10%
120 -	Viburnum lantana	Bushy	0.4Citr Double Staggered at 0.3m offset	10%
Total :1200 -				

SPECIFICATION


All works generally, to comply with the written Soft Landscape Specification.

NOTES:

DO NOT SCALE FROM DRAWING
NOT FOR CONSTRUCTION, FOR PLANNING PURPOSES ONLY

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on sheet 1
- Proposed formal hedge planting to be planted in a double staggered row 300mm apart and at 400mm centres in each row. To be maintained at 1m height
- Proposed mixed native hedge planting to be planted in a double staggered row 300mm apart and at 400mm centres in each row. To be maintained at 1m height and 1.8m height adjacent to boundaries. Strained wire fences, is to be erected to run through the centre of the proposed hedgerow.
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed native mix shrub planting to be planted in groups of 5-7no. of each species and as above
- Proposed Species Rich Grassland Meadow to be seeded with General Purpose Meadow EM1 Mixture as supplied by Emorsgate and sown at 4 grams per msq, or similar and approved.
- Proposed meadow grassland to be seeded with EW1 Woodland Mixture as supplied by Emorsgate and sown at 4 grams per msq, or similar and approved.
- Proposed Amenity Grass areas to receive good quality amenity grass turves laid in line with good horticultural practices and seeded with A19 Mixture where appropriate
- Proposed SuDs to be seeded with EM8 seed mix as supplied by Emorsgate Seeds and sown at 4 grams per msq, or similar and approved
- Proposed 400mm wide 75mm depth bark mulch strip to abut planting adjacent to sides or ends of parking bays
- Cut lines - See sheet location plan on sheet 4
- Services
 - Proposed position of Storm Water Sewer & Inspection Chamber. See drainage engineer design for details.
 - Proposed position of Foul Sewer & Inspection Chamber. See drainage engineer design for details.
 - Proposed position of Underground Attenuation Tank. See drainage engineers design for details.
 - Proposed position of Foul Drain. See drainage engineers design for details.
 - Proposed position of Street Lighting Column. See lighting engineers design for details
- Planting Schedule on Sheet 2



Rev Date Details Drawn



HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

4 & 5 The Old Mill, Fry's Yard, Bridge Street,
Codalming, GU7 1HP
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close,
Eastleigh, SO50 9SX
Tel: 02382 026300

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

Vistry Homes

scheme: Boorley Green Gateway
Winchester Road, Botley

client: Vistry Homes

drawing: Open Space Proposals

date: May 2022

scale: 1:200@A1

drawing no: VYH23647 21 Sheet 2

drawn: LS/RH checked: DKM

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.