

EXTERNAL WORKS

1. REFER TO CIVIL AND STRUCTURAL SPECIFICATION REPORT - PARTS D & Q.
- RETENTION:
2. THE DRAWING ILLUSTRATES SUGGESTED METHODS FOR RETENTION. CONTRACTOR SHOULD SUBMIT PROPOSALS FOR SUGGESTED AND/OR ALTERNATIVE METHODS OR WHERE NO SUGGESTIONS HAVE BEEN MADE.
3. REFER TO SEPARATE DRAWING FOR PARAMETERS RELATING TO SUPPLIERS DESIGNING PRE-CAST 'U' SHAPED RETAINING WALL UNITS.
4. WHERE RETENTION IS TO BE INSTALLED ALONG THE SITE BOUNDARY THE CONTRACTOR MUST CONFIRM SETTING OUT OF THE BOUNDARY WITH THE ARCHITECT.
5. GUARDRAILS, FENCING AND VEHICLE BARRIERS SHOULD BE ALLOWED FOR AND COORDINATED WITH ARCHITECT.
- EARTH SLOPES
6. ALLOW FOR A MINIMUM 0.5m FLAT VERGE BEFORE SLOPING UP OR DOWN FROM THE KERB EDGE.
7. FOR SLOPES STEEPER THAN 1:3 ALLOW FOR PINNING EROSION CONTROL MATTING TO FACE TO COMPLEMENT THE PLANTING SCHEME.
- KERBS:
8. SETTING OUT OF THE EXTERNAL AREA IS THE RESPONSIBILITY OF THE ARCHITECT AND MUST BE CHECKED ON SITE BY THE CONTRACTOR. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ARCHITECT.
9. CONTRACTOR SHOULD INSTALL QUADRANTS ON EXTERNAL CORNERS OF RAISED KERBS WHERE POSSIBLE TO AVOID SHARP CORNERS.
10. ACCESS COVERS WITHIN BLOCK PAVING SHOULD BE RECESSED TO ALLOW CONTINUOUS LAYING OF BLOCKS.
11. CONTRACTOR TO NOTIFY ENGINEER WHERE THERE IS POTENTIAL FOR A RAISED KERB TO CREATE A FALL TOWARD THE BUILDING.
- GENERALLY:
12. ALL WORKS INCLUDING EXCAVATIONS AND TEMPORARY WORKS MUST REMAIN WHOLLY WITHIN THE SITE.
13. EXCAVATIONS SHOULD NOT UNDERMINE NEIGHBOURING STRUCTURE OR PAVING. IF THE CONTRACTOR IS IN ANY DOUBT HE MUST NOTIFY THE DESIGN TEAM IMMEDIATELY.
14. EXCAVATIONS SHOULD BE KEPT FREE OF STANDING WATER DURING CONSTRUCTION. REFER TO THE SITE INVESTIGATION REPORT FOR GROUND WATER LEVELS ALTHOUGH NOTE THAT LEVELS ARE SEASONAL. ALLOW FOR SUMP AND PUMPING WHERE NECESSARY.
15. EVERY EFFORT HAS BEEN MADE TO ASCERTAIN TYPE, LOCATION AND DEPTH OF BURIED SERVICES AND/OR OBSTRUCTIONS. HOWEVER, THE CONTRACTOR IS ADVISED TO CARRY OUT OWN INVESTIGATIONS TO ENSURE THERE ARE NO CLASHES WITH THE PROPOSED WORKS.
16. CONTRACTOR IS RESPONSIBLE FOR PROTECTING RETAINED SERVICES AND MAKING CONTACT WITH OWNERS OF APPARATUS TO OBTAIN NECESSARY CONSENT FOR EXCAVATION, PROTECTION AND/OR DIVERTING. BURIED OBSTRUCTIONS ENCOUNTERED DURING EXCAVATION THAT CONFLICT WITH PROPOSED WORKS SHOULD BE BROKEN OUT AND REMOVED. RESIDUAL VOIDS TO BE BACKFILLED AND COMPACTED AS PER SPECIFICATION.

LEGEND

- SITE BOUNDARY
- DRAINAGE:
- LINEAR DRAINAGE CHANNEL
- KERB DRAIN
- KERBS:
- ALSO REFER TO DETAILS
- H2 RAISED KERB H100mm TO 125mm
- BN RAISED KERB H5mm TO H100mm
- BN DROPPED KERB H5mm
- CS FLUSH KERB H0mm
- EF EDGING KERB H0mm TO H100mm
- RETENTION:
- SLAB ON EDGE H250mm TO H400mm

C4	29.11.22	UPDATED TO SUIT LATEST SITE LAYOUT, REVISION AS CLOUSED	NM	IL
C3	19.08.22	UPDATED TO SUIT LATEST SITE LAYOUT, REVISION AS CLOUSED	AR	IL
C2	07.07.22	UPDATED TO SUIT LATEST SITE LAYOUT, REVISION AS CLOUSED	SH	IL
C1	16.06.22	ISSUED FOR CONSTRUCTION	AR	IL

LEVELS & EXTERNAL WORKS

Rev	Date	Description	Technician	Reviewer
C4	29.11.22	UPDATED TO SUIT LATEST SITE LAYOUT, REVISION AS CLOUSED	NM	IL
C3	19.08.22	UPDATED TO SUIT LATEST SITE LAYOUT, REVISION AS CLOUSED	AR	IL
C2	07.07.22	UPDATED TO SUIT LATEST SITE LAYOUT, REVISION AS CLOUSED	SH	IL
C1	16.06.22	ISSUED FOR CONSTRUCTION	AR	IL



I&L CONSULTING Ltd.
E: projects@iconsultants.com

Project	Project Number	Drawing Number	Revision
WOODSIDE ROAD, EASTLEIGH	22-007-MAR	G01	C4