

HYDROBRAKE FLOW CONTROL – Manhole Schedule				
Chamber No.	Flow Restriction (L/s)	Design Depth (m)	Invert Level (m)	Unit Reference
SWMH33	5.00	1.750	25.754	SHE–0095–5000–1750–5000
SWMH37	10.00	2.000	23.806	SHE–0131–1000–2000–1000
SWMH46	15.00	2.200	22.024	SHE–0157–1500–2200–1500
FLOW CONTROL CHAMBER 01	1.00	1.425	21.075	SHE–0043–1000–1425–1000
SWMH54	3.00	0.886	22.782	SHE–0084–3000–0886–3000
SWMH48	8.00	1.446	21.080	SHE–0125–8000–1446–8000
FLOW CONTROL CHAMBER 02	29.60	0.950	20.300	SHE–0236–2960–0950–2960
SWMH78	3.00	1.361	23.080	SHE–0077–3000–1361–3000
SWMH73	1.50	1.352	22.920	SHE–0054–1500–1352–1500
FLOW CONTROL CHAMBER 03	13.60	1.050	18.550	SHE–0167–1360–1050–1360
SWMH105	1.50	1.462	21.100	SHE–0053–1500–1466–1500
SWMH115	2.00	1.785	20.480	SHE–0058–2000–1785–2000
SWMH128	0.80	1.400	19.820	SHE–0038–8000–1400–8000

DISCLAIMER NOTES:

- THIS DOCUMENT IS COPYRIGHT OF THE ORIGINATOR AND MUST BE TREATED AS CONFIDENTIAL.
- THIS DOCUMENT MUST NOT BE ALTERED, REPRODUCED OR DISTRIBUTED WITHOUT PRIOR WRITTEN CONSENT OF THE ORIGINATOR
- THIS DOCUMENT MUST NOT BE ALTERED - THE ORIGINATOR ACCEPTS NO RESPONSIBILITY FOR ANY DISCREPANCIES ARISING AS A RESULT OF THE ORIGINATORS INFORMATION BEING ALTERED BY OTHERS
- ANY DISCREPANCY MUST BE REPORTED TO THE ORIGINATOR
- DO NOT SCALE THIS DOCUMENT - USE FIGURED DIMENSIONS ONLY
- ALL DIMENSIONS MUST BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY RELATED WORKS
- THIS DOCUMENT MUST BE READ IN CONJUNCTION WITH ALL SUPPORTING DOCUMENTS PRODUCED BY THE ORIGINATOR AND OTHER PROJECT DISCIPLINES
- THE ORIGINATOR ACCEPTS NO RESPONSIBILITY FOR THE ACCURACY OF BACKGROUND INFORMATION PRODUCED BY THIRD PARTIES - THIS MUST BE TREATED AS INDICATIVE ONLY
- USERS OF THIS DOCUMENT ARE RESPONSIBLE FOR CHECKING WHICH REVISION IS CURRENT
- THE DOCUMENT STATUS "INFORMATION" OR "PRELIMINARY", INDICATES THAT THIS DRAWING IS FOR REFERENCE PURPOSES ONLY - THE ORIGINATOR WILL ACCEPT NO RESPONSIBILITY FOR THE COMPLETENESS OF INFORMATION UNDER THIS STATUS
- THE DOCUMENT STATUS "RECORD" OR "AS BUILT" HAS BEEN PREPARED, IN PART, BASED UPON INFORMATION FURNISHED BY OTHERS. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, THE ORIGINATOR ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THIS "RECORD" OR "AS BUILT" DOCUMENT OR FOR ANY ERRORS OR OMISSIONS THAT MAY HAVE BEEN INCORPORATED INTO IT AS A RESULT OF INCORRECT INFORMATION PROVIDED TO THE ORIGINATOR. THOSE RELYING ON THE "RECORD" OR "AS BUILT" DOCUMENT ARE ADVISED TO OBTAIN INDEPENDENT VERIFICATION OF ITS ACCURACY

DRAWING NOTES:

CDM REGULATIONS 2015

SIGNIFICANT OR NON-OBVIOUS RISKS AND RISKS WHICH ARE DIFFICULT TO MANAGE ARE IDENTIFIED ON THIS DRAWING USING THE FOLLOWING SYMBOL. IDENTIFIED TO THE RIGHT WITH BRIEF ACCOMPANYING TEXT. FOR FURTHER DETAILS OF THE RISKS IDENTIFIED BY DESIGNERS, REFERENCE SHOULD BE MADE TO CDM HAZARD REGISTER.

EXTERNAL REFERENCES:

THIS INFORMATION & RIDGE & PARTNERS LLP CIVIL 3D & ASSOCIATED 3D OUTPUTS ARE BASED UPON THE FOLLOWING INFORMATION FROM THE DESIGN TEAM

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THIS INFORMATION IS CURRENT PRIOR TO CONSTRUCTION

T02

INVERT LEVELS CORRECTED

06/06/2023

LW

T01

ISSUED FOR TENDER

19/06/2023

PO

REV

DESCRIPTION

DATE

DRAWN

ORIGINATOR:

RIDGE

CLIENT:

EASTLEIGH

BOROUGH COUNCIL

IN ASSOCIATION WITH:

PROJECT:

PROPOSED RESIDENTIAL DEVELOPMENT

ONE HORTON HEATH

FIRST RESIDENTIAL PARCEL

TITLE:

SURFACE WATER

FLOW CONTROL SCHEDULE

TECH:

PO

CSE:

Issue

Revised Date

19/06/23

06/07/23

ICSE:

Issue

Revised Date

19/06/23

06/07/23

SCALE: NTS

@ A1

INITIAL ISSUE: 19/06/2023

STATUS:

D2 - SUITABLE FOR TENDER

DRAWING No:

PROJECT:

5015560

ORG:

RDG

ZONE:

XX

LEVEL:

ST

TYPE:

DR

ROLE:

C

NUMBER:

0564

REV:

T02