Native hedge NH1 - Mix 1
north and north east boundary;

121 m2 @ 5 per m2 - 605 in total

65 of each of following:
Acer campestre, Corylus avellana, Crataegus monogyna, Fagus sylvatica, Ilex aquifolium, Prunus spinosa, Sorbus acuparia

75 climbers of each;
Rosa canina
Lonicera periclymenum

1 No. Crataegus laevigata
2 No. Prunus 'Snow Goose'

Native transplant mix - NT 1
15 sqm @ 2 / sqm = 30 plants
Post and wire fenced off area.
Refer to Note

1 No. Frangula alnus, Alder Buckthorn
1 No. Prunus spinosa, Blackthorn
1 No. Crateagus monogyna, Hawthorn

1 No. Prunus padus
Bird cherry

Native transplant mix - NT 2
13sqm @ 2 / sqm = 26 plants
Post and wire fenced off area
Refer to Note

1 No. Prunus padus
Bird cherry
1 No. Sorbus intermedia 'Brouwers'

Native transplant mix - NT 3
22sqm @ 2 / sqm = 44 plants
Post and wire fenced off area
Refer to Note

1 No. Prunus spinosa, Blackthorn
1 No. Frangula alnus, Alder Buckthorn
1 No. Crateagus monogyna, Hawthorn

Existing hedge to be retained

2 Malus sylvestris
Crab Apple

1 No. Crataegus laevigata 'Pauls Scarlett'
1 No. Sorbus intermedia 'Brouwers'

12INCH ESSO

1 No. Sorbus aucuparia, Mountain Ash

Car Port, Groundcover.
(16 per border)
32 Vinca minor
Climbers: 4 Vitis coignetiae

Native transplant mix - NT 4
56 sqm @ 2 / sqm = 112 plants
Post and wire fenced off area
Refer to Note

red peg

Existing Oak Lodge Plot 7

Plot 8
5b 10p

O Hedge 1

WF 1
Wild Flower Area

1 Malus 'Rudolf'

Low planting to front on house

42 Lavandula 'Hidcote'

1 No. Sorbus intermedia 'Brouwers'
1 No. Carpinus betulus

2 No. Acer campestre 'Streetwise'

1 Catalpa bignonioides 'Nana'

Plot 6
5b 8p

1 Prunus 'Snow Goose'

Low Planting to front of house
Herb. Perennial Border
5 x Anemone 'Honorine Joubert' (Ahj)
5 x Penstemon 'Chester 'Scarlett' (Pcs)
3 x Peony 'Sarah Bernhardt' (Psr)
7 x Phlox 'Aida' (Pha)
7 x Rudbeckia fulgida 'Goldsturm'(RfG)
5 Helleborus orientalis (HOr)
3 Cistus xpurpurea

Plot 5
5b 8p

GPS1

1 No. Pinus sylvestris
1 No. Multi Stemmed Betula albosinensis 'Fascination'
1 No. Magnolia 'Leonard Messel'

O Hedge 2

Native transplant mix - 12 No. plants
120-150cm to strengthen boundary in gaps between trees along eastern boundary. Plant outside of root protection areas of veteran trees.

Mixed evergreen hedge - Mix 2:
3 per lin. metre-15 of each
mix through border
Ilex aquifolium
Ligustrum japonicum
Ilex altaclarensis
'Argentea Marginata'

Low Planting to front of house
Herb. Perennial Border
5 x Anemone 'Honorine Joubert' (Ahj)
5 x Penstemon 'Chester 'Scarlett' (Pcs)
3 x Peony 'Sarah Bernhardt' (Psr)
7 x Phlox 'Aida' (Pha)
7 x Rudbeckia fulgida 'Goldsturm'(RfG)
5 Helleborus orientalis (HOr)

1 No. Liquidamber styraciflua 'Worplesdon'

4 No. Tilia cordata 'Greenspire'

Amokura House

STABLES

WF 2
Wild Flower Area

1 No. Quercus robur

Plot 4
3b 6p

1 No. Acer campestre 'Streetwise'

1 No.Prunus avium 'Plena'

1 No. Ilex aquifolium

3 No. Acer platanoides 'Crimson Sentry' with root barriers

1 to 8

Shrub border;
5 Genista lydia
3 Cistus xpurpureus
5 Viburnum 'Compactum'
3 Chaenomeles 'Pink Lady'
10 Lavandula 'Hidcote'

1 No. Quercus robur
1 Magnolia xloebneri 'Leonard Messel'

1 No. Crataegus laevigata

1 No. Prunus subhirtella 'Autumnalis Rosea'
1 No. Amelanchier 'Robin Hill'

1 Malus huphensis

O Hedge 3
O Hedge 4

2 No. Sorbus acuparia 'Streetwise'

White Lodge

Native hedge NH2 - Mix 1
western boundary and to west side of entrance;

109 m2 @ 5 per m2 - 545 in total

58 of each of following:
Acer campestre, Corylus avellana, Crataegus monogyna, Fagus sylvatica, Ilex aquifolium, Prunus spinosa, Sorbus acuparia

70 climbers of each;
Rosa canina
Lonicera periclymenum

WF 3
Wild Flower Area

1 No. Quercus robur

2 No.Sorbus acuparia 'Streetwise'

1 No. Carpinus betulus
1 No. Ilex aquifolium

WF 4
Wild Flower Area

1 No. Ilex aquifolium

2 No. Prunus 'Snow Goose'

1 No. Tilia cordata 'Greenspire'

1 No. Pinus sylvestris

Plot 1
5b 8p

Plot 2
5b 8p

Plot 3
5b 8p

2 No. Prunus 'Snow Goose'

2 No. Betula albosinensis 'Fascination'

Native transplant mix - NT 5
54 sqm @ 2 / sqm = 108 plants

Native hedge NH3 - Mix 1
South-west side of entrance;

30 m2 @ 5 per m2 - 150 in total

15 of each of following:
Acer campestre, Corylus avellana, Crataegus monogyna, Fagus sylvatica, Ilex aquifolium, Prunus spinosa, Sorbus acuparia

22 Climbers of each;
Rosa canina
Lonicera periclymenum

O Hedge 5
O Hedge 6

Low Planting to side of house
7 Liriope muscari
5 Polystichum setiferum
7 Geranium pratense 'Mrs Kendall Clark'

1 No. Quercus robur

Existing tree line to be thinned and low grade trees/shrubs to be removed. New hedge to be proposed to thicken the boundary.

1 No. Ilex aquifolium

Native hedge NH4 - Mix 1
west side of entrance;

34 m2 outside and 33 m2 inside of fence @ 5 per m2 - 335 in total

36 of each of following:
Acer campestre, Corylus avellana, Crataegus monogyna, Fagus sylvatica, Ilex aquifolium, Prunus spinosa, Sorbus acuparia

42 Climbers of each;
Rosa canina
Lonicera periclymenum

Gas Governor
Gas Board Sub station

Bridge Road A 27

18 52 51 50 49 47 45 3 1 2

KEY

- Veteran Trees
- Trees to be removed
- Trees to be retained
- Tree Root protection area
- New trees All to be mulched 75mm min depth
- Lawn to dwellings to rear and front gardens
- Long mown wildflower grass meadow - see note on drawing
- Ornamental hedge
- Low level planting to front of dwellings
- Native Hedgerow NH ref. See note on drawing
- Evergreen hedge - Mix 2
- Existing hedge to be retained
- Native Transplants with wire fence NT ref. See note
- Climbers
- Permeable block paving
- Concrete flag paving
- Flexible footway asphalt
- Cobble setts
- Impermeable block paving

NOTES

New Ornamental hedge
Carpinus betulus Hornbeam
Single row @ 450mm c/c
Ca 156 plants in total

O Hedge	Length	No
1	16.7	37
2	16.2	36
3	7	16
4	7	16
5	11.5	27
6	2.5	6

Wild flower planting
4 large areas as shown on plan. Allow for 1m wide mown grass strip to edges of roads and paths.

Mix to provide a pollen rich, insect friendly and environmentally reliable food source for birds and insects. Seed mix to be wild flower and grasses - BS4P loam and alluvial seed mixture.
The 4 areas of wild flower shown measure ca 5619 sqm in total
Seed mix to be sown at quantities recommended by supplier (ca 3gms / sqm).

Wild Flower Areas shown:

WF1	892 sqm
WF2	910 sqm
WF3	2337 sqm
WF4	1485 sqm

Native Transplant Mix -

Small groups of native transplants planted behind boundary hedge
Each area to be protected with post and wire fence to allow clear access for maintenance.
Preferred size to be 120-150cm to strengthen visual barrier.
Pit plant carefully / by hand to avoid roots of existing trees.

Planting bed to be bark mulched, min 75mm in depth
NT - References (see drawing)

160 sqm @ 2 / sqm = 320 trees planted in these quantities:

Corylus avellana	41
Crataegus monogyna	41
Prunus spinosa	41
Prunus domestica	41
Pyrus communis	41
Sambucus nigra	41
Sorbus torminalis	41
Clematis vitalba	11
Lonicera periclymenum	11
Rosa arvensis	11

Native Hedge - Mix 1

Native mixed plants planted in double staggered rows @400mm centre

327 sqm @ 5 / sqm = 1635 made up of the following shrubs:

Acer campestre	174
Corylus avellana	174
Crataegus monogyna	174
Fagus sylvatica	174
Ilex aquifolium	174
Prunus spinosa	174
Sorbus acuparia	174
Rosa canina	209
Lonicera periclymenum	209

Evergreen Hedge - Mix 2

3 / linear metre = 45 shrubs

made up of the following shrubs:

Ilex aquifolium	15
Ligustrum japonicum	15
Ilex altaclarensis 'Argentea Marginata'	15

notes:

Refer to drawing 1107 for Planting Schedule
Refer to drawing 1108 for Landscape plan with drainage overlay

revisions:

A	12.08.2022	GR	Landscape plan updated
B	13.12.2022	GR	Landscape plan updated
C	10.01.2023	GR	Landscape plan updated
D	10.09.2023	GR	New access road added & landscaping amended
E	22.09.2023	GR	Plot 4 parking amended

0 100mm @A1

NOTE: The contractor is responsible for checking all site dimensions and levels. These should be checked prior to the ordering of any components and before the commencement of the works. All discrepancies should be brought to the attention of the Contract Administrator

Capital Homes

Bridge Road

Bursledon

drawing information

title: Landscape plan
status: Planning
date: August 2022
scale: NTS
drawn: GR
chk'd: SCR

R & R DESIGN STUDIO LTD

job: 1122 dwg: 1106 rev: E