

St Leonards Church, Old Bursledon. Tree works schedule October 2023

Tree no.	Species	Location	Preliminary Recommendations	Priority rating	Notes
T10	Yew	Old churchyard, yew to west of church.	Remove hanger	1- within 6 months.	
T1	Ash	Northwest boundary	Fell	1- within 6 months.	
G4	Ash + dead ivy clad one to west.	Northwest boundary	Fell	1- within 6 months.	
T6	Ash	Open grown in central churchyard	Fell	1- within 6 months.	
T8	Ash	North boundary, east of pine.	Fell	1- within 6 months.	
G3	Mixed including laurel, yew, western red cedar	Along Church Lane	Lift to 2.5m above ground level on churchyard side and 4.5m over Church Lane to allow access and highway clearance. Reduce likelihood of future damage to gravestones.	2- within 1 year	
G5	Mixed including Norway maple, holm oak, yew	Along northern boundary	Lift to 2.5m above ground level on churchyard side and 4.5m over Church Lane to allow access and highway clearance. Reduce likelihood of future damage to gravestones. Lift to clear fence line by 1.0 along length including removal of any small diameter stems (<80mm dia) to a height of 2.5m. To reduce likelihood of damage to fence.	2- within 1 year	
T7	Oak	Open grown central churchyard	Lift to 2.5m above ground level over churchyard including removal of one lower lateral on north side c. 120mm diameter.	2- within 1 year	
T9	Oak	Central northern boundary	Fell. Replant with native oak on top of bank	2- within 1 year	

St Leonards Church, Old Bursledon. Tree works schedule October 2023

Tree no.	Species	Location	Preliminary Recommendations	Priority rating	Notes
T11	Western red cedar	West end of old churchyard	Re-reduce to historic reduction points at c 10m	2- within 1 year	This tree had dropped several branches from this reduction point in the last 5 years so take care if anchoring near reduction points
T14	Beech	Southwest of reading room	Lift to clear by 2-2.5m	2- within 1 year	
G15	Laurel	East of reading room	Lift and cut back to clear by 2-2.5m	2- within 1 year	
G16	2 x ash	Eastern boundary	Check condition in July 2024 to confirm presence of Chalara. If confirmed, fell as public footpath runs below.	2- within 1 year	
G2	2 x wrc	Either side of west gate to new churchyard	Lift to 2.5m above ground level to allow access and reduce oppression. Reduce likelihood of future damage to gravestones.	3- within next inspection interval	
T12	Hazel	By stone bag	Recoppice to near ground level	3- within next inspection interval	
T13	Laurel	Southern boundary, extending nearly to path	Fell to near ground level	3- within next inspection interval	
T17	Ash	On bank by footpath, east of church	Fell	Urgent, as soon as reasonably practicable. 5-day notice granted by Eastleigh Borough Council by Paul on 31.10.23.	URGENT: Timber will be compromised: assume Chalara is present. Take care when felling as may disintegrate.