

Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_LS_1_1
Grid Ref: 451181, 114198

Map Name: National Grid

Map date: 1987

Scale: 1:2,500

Printed at: 1:2,500



Surveyed 1959
Revised 1985
Edition N/A
Copyright 1987
Levelled 1959

Surveyed 1959
Revised 1986
Edition N/A
Copyright 1987
Levelled 1959

Surveyed N/A
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A

Surveyed N/A
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_LS_1_1
Grid Ref: 451181, 114198

Map Name: National Grid

Map date: 1988-1993

Scale: 1:2,500

Printed at: 1:2,500



Surveyed N/A
Revised N/A
Edition N/A
Copyright 1988
Levelled N/A

Surveyed 1993
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A

Surveyed 1993
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A

Surveyed 1993
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A



Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_LS_2_1
Grid Ref: 451806, 114198

Map Name: County Series

Map date: 1868-1869

Scale: 1:2,500

Printed at: 1:2,500



Surveyed 1868
Revised 1868
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1868
Revised 1868
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1868
Revised 1868
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1869
Revised 1869
Edition N/A
Copyright N/A
Levelled N/A




Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_LS_2_1
Grid Ref: 451806, 114198

Map Name: County Series

Map date: 1868-1869

Scale: 1:2,500

Printed at: 1:2,500



Surveyed 1868
Revised 1868
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1869
Revised 1869
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1869
Revised 1869
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1869
Revised 1869
Edition N/A
Copyright N/A
Levelled N/A




Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_LS_2_1
Grid Ref: 451806, 114198

Map Name: County Series

Map date: 1896

Scale: 1:2,500

Printed at: 1:2,500



Surveyed 1896
Revised 1896
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1896
Revised 1896
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1896
Revised 1896
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1896
Revised 1896
Edition N/A
Copyright N/A
Levelled N/A




Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-911-MM7-251-KOY_LS_2_1
Grid Ref: 451806, 114198

Map Name: County Series

Map date: 1909

Scale: 1:2,500

Printed at: 1:2,500



Surveyed 1909
Revised 1909
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1909
Revised 1909
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1909
Revised 1909
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1909
Revised 1909
Edition N/A
Copyright N/A
Levelled N/A




Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-911-MM7-251-KOY_LS_2_1
Grid Ref: 451806, 114198

Map Name: National Grid

Map date: 1965

Scale: 1:2,500

Printed at: 1:2,500



Surveyed N/A
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1964
Revised 1964
Edition N/A
Copyright 1965
Levelled 1959

Surveyed N/A
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1964
Revised 1964
Edition N/A
Copyright 1965
Levelled 1959




Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_LS_2_1
Grid Ref: 451806, 114198

Map Name: National Grid

Map date: 1987

Scale: 1:2,500

Printed at: 1:2,500



Surveyed 1959
Revised 1986
Edition N/A
Copyright 1987
Levelled 1959

Surveyed 1959
Revised 1986
Edition N/A
Copyright 1987
Levelled 1959

Surveyed N/A
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A

Surveyed N/A
Revised 1986
Edition N/A
Copyright 1987
Levelled 1959




Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-911-MM7-251-KOY_LS_2_1
Grid Ref: 451806, 114198

Map Name: National Grid

Map date: 1993

Scale: 1:2,500

Printed at: 1:2,500



Surveyed 1993
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A

Surveyed 1993
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A

Surveyed 1993
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A

Surveyed 1993
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A




Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025


Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf





Groundsure
INSIGHTS

Landline Scale Grid Index



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_Landline_1_1
Grid Ref: 451344, 114048

Map Name: LandLine

Map date: 2003

Scale: 1:1,250

Printed at: 1:1,250




Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_Landline_2_1
Grid Ref: 451644, 114048

Map Name: LandLine

Map date: 2003

Scale: 1:1,250

Printed at: 1:1,250



Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

HOLLY TREE FARM,
MADDOXFORD LANE, BOTLEY,
HAMPSHIRE, SO32 2DB

Client Ref: GE23094/ PO-8774
Report Ref: GS-91I-MM7-251-KOY_Landline_2_2
Grid Ref: 451644, 114348

Map Name: LandLine

Map date: 2003

Scale: 1:1,250

Printed at: 1:1,250



Produced by
Groundsure Insights
T: 08444 159000
E: info@groundsure.com
W: www.groundsure.com

© Crown copyright and database rights 2024 Ordnance Survey 100035207

Production date: 12 June 2025

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



APPENDIX B

Exploratory Hole Logs & In-situ Test Results





Geo-Environmental www.gesl.net

Unit 7, Danworth Farm
Hurstpierpoint
BN6 9GL

Borehole Log

Borehole No.

BH01

Sheet 1 of 3

Project Name: Holly Tree Farm

Project No.
GE23094

Co-ords: 451561E - 114203N

Hole Type
CP

Location: Boorley Green

Level: 17.78

Scale
1:50

Client: Bloor Homes Southern

Dates: 11/08/2025

Logged By
Driller

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
		Depth (m)	Type	Results					
					0.10	17.68		Topsoil	
								TOPSOIL	
								Firm orange brown very gravelly CLAY	
								RIVER TERRACE DEPOSITS	
		0.80	B		0.90	16.88		Dense orange brown SAND and GRAVEL	1
		1.00	B						
		1.50 - 1.81	B						2
		1.50	C	N=50 (6,9/18,21,11,0)					
		2.50 - 2.95	B						
		2.50	C	N=43 (2,9/18,18,2,5)					
		3.00	B		3.00	14.78		Medium dense yellowish brown clayey fine SAND	3
		3.00	B						
		3.50 - 3.95	B						4
		3.50	C	N=30 (3,3/4,5,9,12)					
		4.50 - 4.95	B						5
		4.50	C	N=32 (3,5/5,5,10,12)					
		5.50 - 5.95	B						6
		5.50	C	N=36 (3,5/7,8,9,12)					
		7.00 - 7.45	B						7
		7.00	C	N=34 (3,6/6,7,9,12)					
		8.50 - 8.95	B						8
		8.50	C	N=40 (3,5/6,9,9,16)					
		10.00 - 10.45	B						9
									10
Continued on Next Sheet									
Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks			
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to				
		8.00	6.00						
									 Status FINAL


 Unit 7, Danworth Farm Hurstpierpoint BN6 9GL www.gesl.net		Borehole Log				Borehole No. BH01 Sheet 2 of 3	
Project Name: Holly Tree Farm		Project No. GE23094		Co-ords: 451561E - 114203N		Hole Type CP	
Location: Boorley Green				Level: 17.78		Scale 1:50	
Client: Bloor Homes Southern				Dates: 11/08/2025		Logged By Driller	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description		
		Depth (m)	Type	Results						
		10.00	C	N=36 (3,5/7,7,10,12)	14.20	3.58		Medium dense yellowish brown clayey fine SAND WITTERING FORMATION		
		11.00 - 11.45	B							11
		11.50	C	N=40 (3,5/8,10,10,12)						12
		13.00 - 13.45	B							13
		13.00	C	N=37 (3,6/6,9,9,13)						14
		14.20	B							15
		14.50 - 14.95	B							16
		14.50	C	N=32 (3,6/6,7,9,10)						17
		16.00 - 16.45	B		14.20	3.58		Dense grey blue green fine SAND with pockets of Clay. WITTERING FORMATION		
		16.00	C	N=38 (3,6/7,9,10,12)						18
		17.50 - 17.95	B							19
		17.50	C	N=35 (3,6/6,7,9,13)					20	
		19.00 - 19.45	B							
		19.00	C	N=42 (3,9/9,10,11,12)						
Continued on Next Sheet										

Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to	
		8.00	6.00			


 Status
 FINAL




 Unit 7, Danworth Farm Hurstpierpoint BN6 9GL www.gesl.net		Borehole Log				Borehole No. BH01 Sheet 3 of 3	
Project Name: Holly Tree Farm		Project No. GE23094		Co-ords: 451561E - 114203N		Hole Type CP	
Location: Boorley Green				Level: 17.78		Scale 1:50	
Client: Bloor Homes Southern				Dates: 11/08/2025		Logged By Driller	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
		Depth (m)	Type	Results					
		20.50 20.50	B C	N=38 (3,6/6,8,10,14)	25.45	-7.67		Dense grey blue green fine SAND with pockets of Clay. WITTERING FORMATION	21
		22.00 - 22.45 22.00	B C	N=40 (6,7/7,9,12,12)					22
		23.50 - 23.95 23.50	B C	N=42 (6,8/8,9,12,13)					23
		25.00 - 25.45 25.00	B C	N=49 (9,10/10,12,12,15)					24
							End of Borehole at 25.45m		25
									26
									27
									28
									29
									30

Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to	
		8.00	6.00			


 Status
 FINAL

 Unit 7, Danworth Farm Hurstpierpoint BN6 9GL www.gesl.net		Borehole Log				Borehole No. BH02 Sheet 1 of 3	
Project Name: Holly Tree Farm		Project No. GE23094		Co-ords: 451455E - 114281N		Hole Type CP	
Location: Boorley Green				Level: 20.97		Scale 1:50	
Client: Bloor Homes Southern				Dates: 11/08/2025		Logged By	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
		Depth (m)	Type	Results					
		0.50 - 1.00	B	N=9 (1,1/2,2,2,3)	0.30	20.67	 Topsoil TOPSOIL  Brown sandy CLAY with gravel/cobbles RIVER TERRACE DEPOSITS	1	
		1.20 - 1.70 1.20	B C						
		2.00 - 2.50 2.00	B C	N=11 (1,1/2,2,3,4)	2.00	18.97	 Brown CLAY with some gravel WITTERING FORMATION	2	
		3.00 - 3.50 3.00	B C	N=13 (1,2/2,3,4,4)	2.70	18.27			
		4.00 4.00	D S	N=15 (1,2/4,4,4,3)	4.30	16.67	 Brown slightly sandy gravelly CLAY WITTERING FORMATION	4	
		4.50 - 5.00	B						
		5.00 5.00	B C	N=12 (1,2/2,3,3,4)	5.00	15.97	 Brown clayey SAND WITTERING FORMATION	5	
		6.00 6.00	D S	N=11 (1,2/3,2,3,3)	9.10	11.87			
		7.50 7.50	D S	N=18 (1,2/3,4,5,6)					
		9.00 9.00	D S	N=28 (3,4/5,7,7,9)	9.10	11.87	 Grey silty SAND WITTERING FORMATION	9	
9.50 - 10.00	B								
Continued on Next Sheet								10	


Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks	 Status FINAL
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to		
		9.30	8.15				

 Unit 7, Danworth Farm Hurstpierpoint BN6 9GL www.gesl.net		Borehole Log				Borehole No. BH02 Sheet 2 of 3	
Project Name: Holly Tree Farm		Project No. GE23094		Co-ords: 451455E - 114281N		Hole Type CP	
Location: Boorley Green				Level: 20.97		Scale 1:50	
Client: Bloor Homes Southern				Dates: 11/08/2025		Logged By	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
		Depth (m)	Type	Results					
		10.50 10.50	D S	N=26 (2,3/4,6,7,9)				Grey silty SAND WITTERING FORMATION	11
		12.00 12.00	D S	N=32 (2,3/5,8,9,10)					12
		13.00 - 13.50	B						13
		13.50 13.50	D S	N=38 (2,4/6,9,11,12)					14
		15.00 15.00	D S	N=46 (2,5/8,10,13,15)					15
		16.00 - 16.50	B						16
		16.50 16.50	D S	N=41 (3,4/7,9,11,14)					17
		18.00 18.00	D S	N=39 (3,5/6,8,10,15)					18
		19.00 - 19.50	B						19
		19.50 19.50	D S	N=40 (4,5/7,9,11,13)					20
Continued on Next Sheet									

Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks	 Status FINAL
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to		
		9.30	8.15				





 Unit 7, Danworth Farm Hurstpierpoint BN6 9GL www.gesl.net		Borehole Log				Borehole No. BH02 Sheet 3 of 3	
Project Name: Holly Tree Farm		Project No. GE23094		Co-ords: 451455E - 114281N		Hole Type CP	
Location: Boorley Green				Level: 20.97		Scale 1:50	
Client: Bloor Homes Southern				Dates: 11/08/2025		Logged By	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
		Depth (m)	Type	Results					
		21.00 21.00	D S	N=43 (3,4/7,9,12,15)				Grey silty SAND WITTERING FORMATION	21
		22.00 - 22.50	B						22
		22.50 22.50	D S	N=47 (4,6/8,10,13,16)					23
		24.00 - 24.50	B						24
		25.00 25.00	D S	N=50 (5,6/9,11,13,17)	25.00	-4.03		End of Borehole at 25.00m	25
									26
									27
									28
									29
									30

Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to	
		9.30	8.15			


 Status
 FINAL

 Unit 7, Danworth Farm Hurstpierpoint BN6 9GL www.gesl.net		Borehole Log				Borehole No. BH03 Sheet 1 of 3	
Project Name: Holly Tree Farm		Project No. GE23094		Co-ords: 451330E - 114127N		Hole Type CP	
Location: Boorley Green				Level: 21.10		Scale 1:50	
Client: Bloor Homes Southern				Dates: 12/08/2025		Logged By	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description		
		Depth (m)	Type	Results						
		0.10 - 0.50	B		0.50	20.60		Topsoil TOPSOIL		
		0.50 - 1.00	B					Soft mottled CLAY WITTERING FORMATION		
		1.20 1.20	D S	N=7 (1,0/1,1,2,3)						
		1.60 - 2.00	B							
		2.00 2.00	D S	N=9 (1,1/2,2,3,2)						
		2.50 - 22.50	D							
		3.00 3.00	D S	N=10 (1,1/2,2,3,3)						
		4.00 4.00	D S	N=14 (1,2/3,3,4,4)						
		4.50 - 5.00	B							
		5.00 5.00	D S	N=21 (2,3/4,5,6,6)						
		5.60 - 6.00	B							Medium dense blueish silty sandy CLAY WITTERING FORMATION
		6.00 6.00	D S	N=22 (2,4/4,5,6,7)						
		7.50 7.50	D S	N=37 (4,5/7,8,10,12)						
		8.00 - 8.50	B							Medium dense blueish sandy CLAY WITTERING FORMATION
		9.00 9.00	D S	N=36 (4,4/7,8,10,11)						
Continued on Next Sheet									10	

Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to	
		9.00	7.91			



 Status
 FINAL

 Unit 7, Danworth Farm Hurstpierpoint BN6 9GL www.gesl.net		Borehole Log				Borehole No. BH03 Sheet 2 of 3	
Project Name: Holly Tree Farm		Project No. GE23094		Co-ords: 451330E - 114127N		Hole Type CP	
Location: Boorley Green				Level: 21.10		Scale 1:50	
Client: Bloor Homes Southern				Dates: 12/08/2025		Logged By	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
		Depth (m)	Type	Results					
		10.50 10.50	D S	N=38 (4,7/7,9,10,12)	15.70	5.40		Medium dense blueish sandy CLAY WITTERING FORMATION	11
		12.00 12.00	D S	N=35 (3,5/6,8,10,11)				12	
		13.00 - 13.50	B					13	
		13.50 13.50	D S	N=40 (3,6/8,10,11,11)				14	
		15.00 15.00	D S	N=40 (3,5/7,9,11,13)				15	
		16.00 - 16.50	B					16	
		16.50 16.50	D S	50 (5,9/10,12,15,13 for 60mm)				17	
		18.00 18.00	D S	50 (5,7/9,13,16,12 for 55mm)				18	
		19.00 - 19.50	B					19	
		19.50 19.50	D S	50 (5,8/10,15,18,7 for 20mm)				20	
Continued on Next Sheet									


Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks	 Status FINAL
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to		
		9.00	7.91				

 Unit 7, Danworth Farm Hurstpierpoint BN6 9GL www.gesl.net		Borehole Log				Borehole No. BH03 Sheet 3 of 3	
Project Name: Holly Tree Farm		Project No. GE23094		Co-ords: 451330E - 114127N		Hole Type CP	
Location: Boorley Green				Level: 21.10		Scale 1:50	
Client: Bloor Homes Southern				Dates: 12/08/2025		Logged By	

Well	Water Strikes	Sample and In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
		Depth (m)	Type	Results					
		21.00 21.00	D S	50 (4,8/11,14,19,6 for 10mm)				Dense blueish SAND WITTERING FORMATION	21
		22.00 - 22.50	B						22
		22.50	S	50 (5,8/11,16,20,3 for 5mm)					23
		24.00 - 24.50	B						24
		25.00 25.00	D S	N=50 (4,7/11,17,22,0)	25.00	-3.90			25
							End of Borehole at 25.00m	26	
								27	
								28	
								29	
								30	


Casing		Water Strikes (mbgl)		Chiselling (mbgl)		Remarks	 Status FINAL
Diameter	Depth (m)	Depth Strike	Rose to	Depth from	Depth to		
		9.00	7.91				



 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: SA01			
	Contract Number: GE23094	Date Started: 07/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1				
	Easting: 451297.4	Northing: 114050.5	Ground Level: 15.60mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25				
Trial Pit Log		Weather: Overcast, warm, dry		Hole Termination:		Stability: Sides stable				
Samples & In Situ Testing			Strata Details						Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description				
0.10	ES1		15.45	0.15		Grass over dark brown sandy CLAY with frequent roots and rootlets				
				(0.45)		TOPSOIL				
0.50	D1	PP=3kg/cm2				Firm to stiff brown and grey mottled CLAY with occasional rootlets				
						LONDON CLAY			0.5	
		PP=2.1kg/cm2	15.00	0.60		Firm orange and grey mottled slightly sandy CLAY. Sand is fine				
						LONDON CLAY				
				(1.10)		Clay land drain			1.0	
1.50	D2	PP=1.8kg/cm2				Firm orange and grey mottled very sandy CLAY. Sand is fine				
						LONDON CLAY			1.5	
			13.90	1.70		Firm orange and grey mottled very sandy CLAY. Sand is fine				
				(0.30)		LONDON CLAY				
2.00	D3	PP=2.4kg/cm2	13.60	2.00		End of Trial Pit at 2.00m			2.0	
									2.5	
									3.0	
									3.5	
Dimensions:					Photo:					
Final Depth:	2.00m									
Final Width:	0.60m									
Final Length:	2.00m									
Remarks										
Groundwater not encountered Soakage										
Water Strikes (mbgl)										
Depth Strike	Rose to				Time Elapsed (mins)					
										
Photo of Pit					Photo of Spoil					

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: SA02		
	Contract Number: GE23094	Date Started: 07/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1			
	Easting: 451367.6	Northing: 114206.8	Ground Level: 25.03mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25			
Trial Pit Log		Weather: Overcast, dry		Hole Termination:			Stability: Sides stable		
Samples & In Situ Testing			Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description			
0.20	ES1	PP=4kg/cm2	24.78	0.25		Grass over dark brown gravelly CLAY with frequent roots and rootlets TOPSOIL		0.5	
0.50	D1			(0.55)		Stiff orange and grey mottled slightly gravelly CLAY with occasional rootlets possibly desiccated. Gravel is fine to medium sub angular to sub rounded of flint RIVER TERRACE DEPOSITS			
1.00	D2	PP=3.5kg/cm2	24.23	0.80		Stiff orange and grey mottled CLAY with rare flint gravel LONDON CLAY			
			24.03	1.00		End of Trial Pit at 1.00m		1.5	
								2.5	
								3.5	
Dimensions:					Photo:				
Final Depth:	1.00m				 PhotoofPit				
Final Width:	0.60m								
Final Length:	1.80m								
Remarks					 PhotoofSpoil				
Groundwater not encountered Soakage									
Water Strikes (mbgl)									
Depth Strike	Rose to		Time Elapsed (mins)						



 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: SA03				
	Contract Number: GE23094	Date Started: 07/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1					
	Easting: 451427.8	Northing: 114139.3	Ground Level: 21.32mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25					
Trial Pit Log				Weather: Overcast, dry, warm		Hole Termination:		Stability: Sides stable			
Samples & In Situ Testing				Strata Details					Water	Backfill	
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description					
0.40 0.50	ES1 D1	PP=3.5kg/cm2	21.12	0.20 (0.80)	   	Grass over dark brown gravelly CLAY with frequent roots and rootlets TOPSOIL Stiff orange and grey mottled slightly gravelly CLAY with occasional rootlets RIVER TERRACE DEPOSITS			0.5		
1.00	D2	PP=3kg/cm2	20.32	1.00		End of Trial Pit at 1.00m			1.0		
									1.5		
									2.0		
									2.5		
									3.0		
									3.5		
Dimensions:					Photo:						
Final Depth:	1.00m				 PhotoofPit						
Final Width:	0.60m										
Final Length:	1.95m										
Remarks					 PhotoofSpoil						
Groundwater not encountered. Soakage											
Water Strikes (mbgl)											
Depth Strike	Rose to		Time Elapsed (mins)								

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: SA04				
	Contract Number: GE23094	Date Started: 07/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1					
	Easting: 451538.6	Northing: 114277.3	Ground Level: 16.58mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25					
Trial Pit Log			Weather: Overcast, dry, warm			Hole Termination:			Stability: Sides stable		
Samples & In Situ Testing				Strata Details						Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description					
0.10	ES1		16.43	0.15		Crop stubble over dark brown slightly silty slightly gravelly CLAY with occasional roots and rootlets					
						TOPSOIL					
0.50	D1	PP=4kg/cm2		(0.55)		Very stiff orange brown CLAY with occasional rootlets and rare flint gravel possible desiccated WITTERING FORMATION				0.5	
			15.88	0.70							
				(0.30)		Very stiff orange brown slightly sandy slightly gravelly CLAY with rare rootlets possibly desiccated WITTERING FORMATION					
1.00	D2	PP=3.8kg/cm2	15.58	1.00		End of Trial Pit at 1.00m				1.0	
										1.5	
										2.0	
										2.5	
										3.0	
										3.5	
Dimensions:						Photo:					
Final Depth:	1.00m					 PhotoofPit					
Final Width:	0.60m										
Final Length:	1.90m										
Remarks						 PhotoofSpoil					
Groundwater not encountered. Soakage											
Water Strikes (mbgl)											
Depth Strike		Rose to		Time Elapsed (mins)							

 Geo-Environmental	Contract Name: Holly Tree Farm		Client: Bloor Homes Southern			Trial Pit ID: SA05		
	Contract Number: GE23094	Date Started: 07/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1		
Trial Pit Log		Easting: 451612.1	Northing: 114230.0	Ground Level: 15.18mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25	
Weather: Overcast, dry, warm			Hole Termination:			Stability: Sides stable		
Samples & In Situ Testing				Strata Details			Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description		
0.40 0.50	ES1 D1	PP=2.9kg/cm2	15.03	0.15		Grass over dark brown slightly silty sandy CLAY with frequent roots and rootlets TOPSOIL	0.5	
				(1.05)		Firm brown very sandy CLAY with occasional rootlets. Sand is fine RIVER TERRACE DEPOSITS		
1.00	D2	PP=1.5kg/cm2	13.98	1.20		Firm orange brown very sandy CLAY. Sand is fine RIVER TERRACE DEPOSITS		
1.40	D3		13.78	1.40		End of Trial Pit at 1.40m	1.5	
							2.0	
							2.5	
							3.0	
							3.5	
Dimensions:				Photo:				
Final Depth:	1.40m			 PhotoofPit				
Final Width:	0.60m							
Final Length:	1.90m							
Remarks				 PhotoofSpoil				
Groundwater not encountered. Soakage								
Water Strikes (mbgl)								
Depth Strike		Rose to	Time Elapsed (mins)					



 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: SA06		
	Contract Number: GE23094	Date Started: 07/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1			
	Easting: 451638.6	Northing: 114204.5	Ground Level: 14.60mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25			
Trial Pit Log									
Weather: Overcast, dry, warm			Hole Termination:			Stability: Sides stable			
Samples & In Situ Testing			Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description			
0.20	ES1	PP=2.5kg/cm2	14.45	0.15		Dark brown sandy CLAY with occasional roots and rootlets TOPSOIL		0.5	
0.50	D1			(0.65)		Firm orange brown sandy CLAY with occasional rootlets RIVER TERRACE DEPOSITS			
1.00	D2	PP=1.6kg/cm2	13.80	0.80		Firm orange brown sandy CLAY RIVER TERRACE DEPOSITS		1.0	
1.50	D3			(0.50)		Firm orange brown very gravelly CLAY. Gravel is fine to coarse sub angular to sub rounded of flint RIVER TERRACE DEPOSITS			
1.80	D4		13.30	1.30		Firm orange brown very gravelly slightly sandy CLAY. Gravel is fine to medium sub angular to sub rounded of flint and sand is fine RIVER TERRACE DEPOSITS		1.5	
			13.00	1.60		Firm orange brown very gravelly slightly sandy CLAY. Gravel is fine to medium sub angular to sub rounded of flint and sand is fine RIVER TERRACE DEPOSITS			
			12.80	1.80		End of Trial Pit at 1.80m		2.0	
								2.5	
								3.0	
								3.5	
Dimensions:									
Final Depth:		1.80m							
Final Width:		0.60m							
Final Length:		1.80m							
Remarks									
Groundwater not encountered Soakage									
Water Strikes (mbgl)									
Depth Strike		Rose to			Time Elapsed (mins)				
Photo:									
									
PhotofPit					PhotofSpoil				

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP01		
	Contract Number: GE23094	Date Started: 12/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1			
	Easting: 451482.4	Northing: 114269.0	Ground Level: 19.79mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25			
Trial Pit Log		Weather: Hot, sunny, dry		Hole Termination:		Stability: Sides stable			
Samples & In Situ Testing			Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description			
0.10	ES1		19.64	0.15		Crop stubble over dark brown slightly sandy slightly gravelly CLAY with frequent roots and rootlets		0.5	
						TOPSOIL			
				(0.45)		Firm orange brown slightly sandy silty CLAY with occasional rootlets			
0.50	D1				WITTERING FORMATION				
			19.19	0.60		Very stiff orange and grey mottled slightly gravelly CLAY with occasional rootlets possibly desiccated			
				(0.60)	WITTERING FORMATION				
1.00	D2	PP=4.5kg/cm2				Stiff orange and grey mottled slightly sandy slightly gravelly CLAY. Gravel is fine to medium sub angular to sub rounded and sand is fine			
1.50	D3	PP=3kg/cm2			WITTERING FORMATION				
			18.59	1.20		Firm orange brown silty CLAY			
				(0.60)	WITTERING FORMATION				
2.00	D4	PP=2.5kg/cm2				Firm orange brown silty CLAY			
			17.99	1.80	WITTERING FORMATION				
				(0.40)		Firm orange brown silty sandy CLAY. Sand is fine			
			17.59	2.20	WITTERING FORMATION				
2.50	D5					Orange brown clayey fine SAND			
			17.19	2.60	WITTERING FORMATION				
				(0.40)					
3.00	D6		16.79	3.00	End of Trial Pit at 3.00m				
Dimensions:					Photo:				
Final Depth:	3.00m				 PhotoofPit				
Final Width:	0.60m								
Final Length:	1.80m								
Remarks					 PhotoofSpoil				
Groundwater not encountered									
Water Strikes (mbgl)									
Depth Strike		Rose to		Time Elapsed (mins)					

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP02		
	Contract Number: GE23094	Date Started: 13/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1			
	Easting: 451632.8	Northing: 114280.0	Ground Level: 14.52mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25			
Trial Pit Log		Weather: Overcast, dry, warm		Hole Termination:		Stability: Localised spalling			
Samples & In Situ Testing			Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description			
0.25	ES1		14.22	(0.30)		Grass over dark brown silty CLAY with occasional roots and rootlets TOPSOIL			
0.50	D1		13.92	(0.30)		Firm orange brown very gravelly CLAY with rare rootlets. Gravel is fine to medium sub angular to sub rounded of flint RIVER TERRACE DEPOSITS		0.5	
1.00	D2		13.12	(0.80)		Orange brown slightly sandy clayey fine to medium sub angular to sub rounded flint GRAVEL RIVER TERRACE DEPOSITS		1.0	
1.50	D3		13.12	(0.80)		Brown clayey fine to coarse sub angular to sub rounded flint GRAVEL RIVER TERRACE DEPOSITS		1.5	
2.00	D4		12.32	(0.50)		Orange and grey fine SAND WITTERING FORMATION		2.0	
2.50	D5		11.82	(0.30)		Light grey fine SAND WITTERING FORMATION		2.5	
3.00	D6		11.52	3.00		End of Trial Pit at 3.00m		3.0	
								3.5	
Dimensions:					Photo:				
Final Depth:	3.00m				 PhotoofPit				
Final Width:	0.60m								
Final Length:	1.80m								
Remarks					 PhotoofSpoil				
Some spalling within the looser gravels. Groundwater not encountered									
Water Strikes (mbgl)									
Depth Strike	Rose to		Time Elapsed (mins)						

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP03			
	Contract Number: GE23094	Date Started: 15/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1				
	Easting: 451290.4	Northing: 114184.7	Ground Level: 23.32mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25				
Trial Pit Log		Weather: Sunny, hot, dry		Hole Termination:			Stability: Sides stable			
Samples & In Situ Testing				Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description				
0.10	ES1		23.17	0.15		Grass over dark brown slightly silty gravelly CLAY with frequent roots and rootlets TOPSOIL				
0.50	D1	PP=2.7kg/cm2		(0.55)		Stiff orange and grey slightly silty CLAY with occasional rootlets LONDON CLAY			0.5	
1.00	D2	PP=2.5kg/cm2		22.62	0.70	Firm to stiff orange and grey silty CLAY LONDON CLAY				
1.00	ES2			(0.90)					1.0	
1.50	D3	PP=1.4kg/cm2		21.72	1.60	Firm brown and grey very silty CLAY LONDON CLAY			1.5	
2.00	D4	PP=1.4kg/cm2		(0.70)					2.0	
2.50	D5			21.02	2.30	Firm purplish grey silty sandy CLAY. Sand is fine LONDON CLAY			2.5	
				(0.40)						
				20.62	2.70	Firm grey silty CLAY LONDON CLAY				
				(0.30)						
3.00	D6		20.32	3.00		End of Trial Pit at 3.00m			3.0	
									3.5	
Dimensions:					Photo:					
Final Depth:	3.00m				 PhotoofPit					
Final Width:	0.60m									
Final Length:	1.80m									
Remarks					 PhotoofSpoil					
Groundwater not encountered										
Water Strikes (mbgl)										
Depth Strike		Rose to		Time Elapsed (mins)						

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP04			
	Contract Number: GE23094	Date Started: 14/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1				
	Easting: 451352.1	Northing: 114188.3	Ground Level: 24.57mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25				
Trial Pit Log		Weather: Cloudy , dry, warm		Hole Termination:		Stability: Sides stable				
Samples & In Situ Testing				Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description				
0.15	ES1		24.37	0.20		Grass over dark brown slightly gravelly sandy CLAY with frequent roots and rootlets				
				(0.40)		TOPSOIL				
0.50	D1	PP=3.5kg/cm2	23.97	0.60		Stiff orange and grey mottled slightly gravelly CLAY with occasional rootlets. Gravel is fine to medium sub angular to sub rounded of flint			0.5	
				(0.60)		RIVER TERRACE DEPOSITS				
1.00	D2	PP=2.5kg/cm2	23.37	1.20		Stiff orange and grey mottled slightly sandy CLAY. Sand is fine			1.0	
				(0.70)		LONDON CLAY				
1.50	D3	PP=1.5kg/cm2	22.67	1.90		Firm to stiff orange and grey silty CLAY			1.5	
				(1.10)		LONDON CLAY				
2.00	D4	PP=1.6kg/cm2				Firm to stiff brown and orange very silty CLAY			2.0	
						LONDON CLAY				
2.50	D5	PP=1.7kg/cm2							2.5	
										
3.00	D6	PP=1.6kg/cm2	21.57	3.00		End of Trial Pit at 3.00m			3.0	
									3.5	
Dimensions:					Photo:					
Final Depth:	3.00m				 PhotoofPit					
Final Width:	0.60m									
Final Length:	1.90m									
Remarks					 PhotoofSpoil					
Groundwater not encountered										
Water Strikes (mbgl)										
Depth Strike		Rose to		Time Elapsed (mins)						

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP05			
	Contract Number: GE23094	Date Started: 14/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1				
	Easting: 451408.2	Northing: 114207.6	Ground Level: 24.20mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25				
Trial Pit Log				Weather: Cloudy, dry, breezy		Hole Termination:		Stability: Sides stable		
Samples & In Situ Testing			Strata Details						Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description				
0.50	D1		23.95	0.25		Grass over dark brown slightly sandy gravelly CLAY with frequent roots and rootlets TOPSOIL			0.5	
				(0.55)		Orange brown clayey fine to coarse sub angular to sub rounded flint GRAVEL with occasional rootlets RIVER TERRACE DEPOSITS				
1.00	D2		23.40	0.80		Orange brown slightly clayey fine to medium sub angular to sub rounded flint GRAVEL RIVER TERRACE DEPOSITS			1.0	
				(0.60)						
1.50	D3	PP=2.9kg/cm2	22.80	1.40		Stiff orange and grey mottled CLAY WITTERING FORMATION			1.5	
2.00	D4	PP=2.7kg/cm2		(1.60)					2.0	
2.50	D5	PP=3.4kg/cm2							2.5	
3.00	D6	PP=3kg/cm2	21.20	3.00		End of Trial Pit at 3.00m			3.0	
3.00	ES1								3.5	
Dimensions:						Photo:				
Final Depth:		3.00m				 PhotoofPit				
Final Width:		0.60m								
Final Length:		1.90m								
Remarks						 PhotoofSpoil				
Groundwater not encountered										
Water Strikes (mbgl)										
Depth Strike		Rose to		Time Elapsed (mins)						

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP06		
	Contract Number: GE23094	Date Started: 13/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1			
	Easting: 451465.0	Northing: 114196.0	Ground Level: 21.95mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25			
Trial Pit Log		Weather: Overcast, dry, warm		Hole Termination:		Stability: Sides stable			
Samples & In Situ Testing			Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description			
0.30	ES1		21.80	0.15		Crop stubble over dark brown slightly sandy gravelly CLAY with frequent roots and rootlets			
0.50	D1	PP=3.4kg/cm2				TOPSOIL			
						Stiff orange and grey gravelly CLAY with occasional rootlets. Gravel is fine to medium sub angular to sub rounded of flint RIVER TERRACE DEPOSITS		0.5	
				(1.05)					
1.00	D2	PP=3.5kg/cm2						1.0	
									
			20.75	1.20		Stiff orange and grey mottled CLAY LONDON CLAY			
1.50	D3	PP=2.8kg/cm2						1.5	
									
				(1.20)					
2.00	D4	PP=2.1kg/cm2						2.0	
2.00	ES2								
									
			19.55	2.40		Stiff orange and grey sandy CLAY. Sand is fine LONDON CLAY		2.5	
2.50	D5	PP=2.1kg/cm2							
									
				(0.60)					
3.00	D6	PP=2kg/cm2	18.95	3.00		End of Trial Pit at 3.00m		3.0	
								3.5	
Dimensions:					Photo:				
Final Depth:	3.00m				 PhotoofPit				
Final Width:	0.60m								
Final Length:	1.90m								
Remarks					 PhotoofSpoil				
Groundwater not encountered									
Water Strikes (mbgl)									
Depth Strike	Rose to		Time Elapsed (mins)						



 Geo-Environmental	Contract Name: Holly Tree Farm		Client: Bloor Homes Southern			Trial Pit ID: TP07	
	Contract Number: GE23094	Date Started: 13/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1	
	Easting: 451537.3	Northing: 114231.3	Ground Level: 18.44mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25	

Weather: Overcast, warm, dry		Hole Termination:		Stability: Sides stable	
------------------------------	--	-------------------	--	-------------------------	--

Samples & In Situ Testing			Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description			
0.50	D1		18.29	0.15		Crop stubble over dark brown slightly sandy gravelly CLAY with occasional roots and rootlets	0.5		
				(0.55)		TOPSOIL			
1.00	D2	PP=3.6kg/cm2	17.74	0.70		Stiff brown gravelly CLAY with occasional rootlets. Gravel is fine to medium sub angular to sub rounded of flint	1.0		
				(0.60)		RIVER TERRACE DEPOSITS			
1.50	D3		17.14	1.30		Stiff orange brown slightly sandy gravelly CLAY. Sand is fine and gravel is fine to medium sub angular to sub rounded of flint	1.5		
				(0.50)		WITTERING FORMATION			
2.00	D4		16.64	1.80		Orange brown clayey sandy fine to medium sub angular to sub rounded flint GRAVEL	2.0		
				(0.50)		WITTERING FORMATION			
2.50	D5		16.14	2.30		Firm orange brown silty sandy gravelly CLAY. Gravel is fine to coarse sub angular to sub rounded of flint and sand is fine to medium	2.5		
				(0.50)		WITTERING FORMATION			
3.00	D6		15.64	2.80		Orange and grey slightly silty clayey fine SAND with occasional layers of firm clay	3.0		
				(0.50)		WITTERING FORMATION			
			15.44	3.00		Yellow and orange fine SAND with frequent layers of firm orange and grey mottled CLAY	3.0		
						End of Trial Pit at 3.00m	3.5		

Dimensions:			Photo:	
Final Depth:	3.00m		 PhotoofPit	
Final Width:	0.60m			
Final Length:	1.90m			
Remarks			 PhotoofSpoil	
Groundwater not encountered				
Water Strikes (mbgl)				
Depth Strike	Rose to	Time Elapsed (mins)		

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP08		
	Contract Number: GE23094	Date Started: 15/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1			
	Easting: 451287.5	Northing: 114132.5	Ground Level: 20.83mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25			
Trial Pit Log		Weather: Sunny, dry, hot		Hole Termination:			Stability: Sides stable		
Samples & In Situ Testing			Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description			
0.30	ES1	PP=3.5kg/cm2	20.68	0.15		Grass over dark brown slightly silty gravelly CLAY with frequent roots and rootlets		0.5	
0.50	D1		20.23	(0.45)		TOPSOIL			
						Stiff light grey and occasionally orange slightly sandy CLAY with rare rootlets			
						LONDON CLAY			
1.00	D2	PP=2.5kg/cm2		0.60		Stiff light grey and purplish grey slightly silty CLAY		1.0	
				(0.50)		LONDON CLAY			
									
									
1.50	D3	PP=2.4kg/cm2	19.73	1.10		Firm to stiff orange and grey silty CLAY		1.5	
				(0.70)		LONDON CLAY			
									
									
2.00	D4	PP=2.5kg/cm2	19.03	1.80		Firm to stiff grey and occasionally orange slightly sandy silty weakly cemented CLAY. Sand is fine		2.0	
2.00	D5			(1.20)		LONDON CLAY			
									
									
2.50	D6	PP=1.6kg/cm2						2.5	
									
									
									
									
			17.83	3.00		End of Trial Pit at 3.00m		3.0	
								3.5	
Dimensions:					Photo:				
Final Depth:	3.00m				 PhotoofPit				
Final Width:	0.60m								
Final Length:	1.90m								
Remarks					 PhotoofSpoil				
Groundwater not encountered									
Water Strikes (mbgl)									
Depth Strike		Rose to		Time Elapsed (mins)					

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP09			
	Contract Number: GE23094	Date Started: 14/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1				
	Easting: 451355.8	Northing: 114144.4	Ground Level: 22.56mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25				
Trial Pit Log		Weather: Cloudy, dry, warm			Hole Termination:			Stability: Sides stable		
Samples & In Situ Testing				Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description				
0.40	ES1		22.36	0.20		Grass over dark brown slightly sandy gravelly CLAY with occasional roots and rootlets	0.5			
0.50	B1		(0.40)		TOPSOIL					
0.50	D1		(0.40)		Orange brown clayey fine to medium sub angular to sub rounded flint GRAVEL with occasional rootlets					
1.00	D2	PP=1.7kg/cm2	21.96	0.60		RIVER TERRACE DEPOSITS	1.0			
1.50	D3	PP=1.2kg/cm2	20.96	1.60		Firm orange and grey silty CLAY	1.5			
2.00	D4	PP=2kg/cm2				(1.10)				WITTERING FORMATION
2.09	1.60		Firm orange and grey silty laminated CLAY	2.0						
2.50	D5	PP=1.6kg/cm2	19.86	2.70		LONDON CLAY	2.5			
						(0.30)				Firm orange and grey mottled silty loosely cemented CLAY
3.00	D6		19.56	3.00			End of Trial Pit at 3.00m	3.0		
Dimensions:					Photo:					
Final Depth:	3.00m				 PhotoofPit					
Final Width:	0.60m									
Final Length:	1.80m									
Remarks					 PhotoofSpoil					
Groundwater not encountered										
Water Strikes (mbgl)										
Depth Strike	Rose to		Time Elapsed (mins)							

 Geo-Environmental	Contract Name: Holly Tree Farm			Client: Bloor Homes Southern			Trial Pit ID: TP10		
	Contract Number: GE23094	Date Started: 14/08/2025	Logged By: FG	Checked By: GR	Status: FINAL	Sheet 1 of 1			
	Easting: 451397.3	Northing: 114131.8	Ground Level: 21.50mOD	Plant Used: JCB	Date Printed: 16/10/2025	Scale: 1:25			
Trial Pit Log		Weather: Cloudy, dry, warm			Hole Termination:		Stability: Sides stable		
Samples & In Situ Testing			Strata Details					Water	Backfill
Depths	Sample ID	Test Result	Reduced Level	Depth (m) (Thickness)	Legend	Strata Description			
0.50	D1	PP=3.5kg/cm2	21.25	0.25		Grass over dark brown sandy CLAY with frequent roots and rootlets TOPSOIL	0.5		
				(0.45)		Stiff orange brown slightly gravelly CLAY with occasional rootlets. Gravel is fine to medium sub angular to sub rounded of flint RIVER TERRACE DEPOSITS			
1.00	B1 D2	PP=2.6kg/cm2	20.80	0.70		Stiff orange and grey slightly gravelly CLAY. Gravel is fine to medium sub angular to sub rounded of flint RIVER TERRACE DEPOSITS	1.0		
1.00				(0.50)		Firm orange and grey silty CLAY LONDON CLAY			
1.50	D3	PP=1.5kg/cm2	20.30	1.20		Firm orange and grey silty CLAY LONDON CLAY	1.5		
				(0.90)					
2.00	D4 ES1	PP=2.3kg/cm2	19.40	2.10		Firm orange and brown slightly silty CLAY LONDON CLAY	2.0		
2.00				(0.90)					
2.50	D5	PP=2.5kg/cm2	18.50	3.00		End of Trial Pit at 3.00m	2.5		
				(0.90)					
3.00	D6	PP=2.6kg/cm2					3.0		
							3.5		
Dimensions:					Photo:				
Final Depth:	3.00m				 14/08/2025 12:41 PhotoofPit				
Final Width:	0.60m								
Final Length:	1.90m								
Remarks					 14/08/2025 12:41 PhotoofSpoil				
Groundwater not encountered									
Water Strikes (mbgl)									
Depth Strike	Rose to		Time Elapsed (mins)						