



- LEGEND**
- BOUNDARIES**
- RESERVED MATTERS SUBMISSION RED LINE
- EXISTING BASELINE FEATURES**
- EXISTING TREES**
Refer to Tyler Grange Tree Constraints plan Ref: 11705_PA2b_Tree Constraints Plan_Overlay.
 - EXISTING VETERAN TREE WITH 16.5M BUFFER**
Refer to Tyler Grange Tree Constraints plan Ref: 11705_PA2b_Tree Constraints Plan_Overlay.
 - EXISTING VEGETATION**
Refer to Tyler Grange Tree Constraints plan Ref: 11705_PA2b_Tree Constraints Plan_Overlay.
 - WATER PIPE EASEMENT**
- FUTURE BASELINE FEATURES**
- FOXWOOD ROAD (SID - Secondary Infrastructure Distributor)**
Planned & permitted but not constructed
 - UPPER ACRE RESIDENTIAL DEVELOPMENT**
Development currently under construction.
- SOFT LANDSCAPE - TREE PLANTING**
- STRUCTURAL TREE PLANTING**
12 - 14cm girth Rootballed
14 - 16cm girth Rootballed
Refer to Plant Schedule for details.
 - WOODLAND TREE PLANTING**
20 - 25cm girth Rootballed
14 - 16cm girth Rootballed
12 - 14cm girth Rootballed
Refer to Plant Schedule for details.
 - WETLAND TREE PLANTING**
12 - 14cm girth Rootballed
Refer to Plant Schedule for details.
 - CAR PARK TREES**
12 - 14cm girth Rootballed
Refer to Plant Schedule for details.
 - FOCAL POINT TREE PLANTING WITHIN SOFTSCAPE**
16 - 18cm girth Rootballed
14 - 16cm girth Rootballed
350-400cm High multistem
Refer to Plant Schedule for details.
 - FEATURE TREE PLANTING WITHIN SOFTSCAPE**
16 - 18cm girth Rootballed
14 - 16cm girth Rootballed
350 - 400cm high
Refer to Plant Schedule for details.
 - PLAZA / FEATURE TREE PLANTING**
14 - 16cm girth Rootballed
Refer to Plant Schedule for details.
 - INDICATIVE HARD TREE PIT**
Location of specialist tree pit - modular suspended pavement system using plastic crates - all size & construction details to be approved by Eastleigh Borough Council
- SOFT LANDSCAPE - STRUCTURAL PLANTING**
- PROPOSED HEDGE PLANTING**
Species rich native and ornamental hedge planting. Native hedge gap up to existing hedgerows. Refer to Plant Schedule for details.
Hedge plants, 2x transplants
Hedging to be planted at 7 plants per linear metre in a double staggered row with 400mm topsoil min, and 550mm subsoil with 50mm bark mulch to surface dressing.
 - PROPOSED PLANTING**
See Plant Schedule for details.
Shrub planting, 5 Litre pots
Herbaceous planting 2, 3 & 5 Litre pots
Shrubs to be planted with 450mm topsoil min, and 550mm subsoil with 50mm bark mulch to surface dressing.
 - PROPOSED TALL MARGINAL PLANTING**
Native herbaceous planting, 3L
See Plant Schedule for details.
Perennials to be planted with 450mm topsoil min, and 550mm subsoil
 - PROPOSED LOWER MARGINAL PLANTING**
Native herbaceous planting, 3L
See Plant Schedule for details.
Perennials to be planted with 450mm topsoil min, and 550mm subsoil
 - PROPOSED RAIN GARDEN PLANTING**
Herbaceous planting, 2 and 3L
See Plant Schedule for details.
To be planted with 450mm topsoil min, and 550mm subsoil with 50mm bark mulch to surface dressing
- SOFT LANDSCAPE - GRASS PLANTING**
- PROPOSED AMENITY GRASS**
Grass seed sown as per manufacturers recommendations over 150mm min. topsoil and 350mm subsoil.
 - PROPOSED WILDFLOWER GRASS**
Grass seed sown as per manufacturers recommendations over 50mm min. low fertility topsoil and 550mm subsoil.
 - PROPOSED NATIVE MEADOW GRASS FOR WET SOIL**
Grass seed sown as per manufacturers recommendations over 50mm min. low fertility topsoil and 550mm subsoil.
- MAINTENANCE ACCESS. PERMEABLE PAVING**
Recycled proprietary reinforced plastic cell system - top soil filled and seeded all constructed to take maintenance vehicles. All to Project engineer's design and specification.
- GRASS PITCH**
Refer to specialist's design for details.

NOTE:

Main contractor to determine exact location of services/drainage, this should be confirmed on site prior to commencement of works to avoid tree pit / services conflicts.

All treatment of softwork areas to comply to BS4428 Code of Practice for general landscape operations.

This drawing assumes that the existing site soil could be re-used. However this is subject to detailed testing and analysis of soil. If the soil is not suitable, imported soil will be required in accordance with the Landscape Specification.

All tree, shrub species supplied for designated areas are to be determined by the proposed planting season. (ie bareroot or container grown stock).

PLEASE REFER TO DRAWING NO. 332613072 OHH-ZZ-00-DR-L-000200, FOR PLANT SCHEDULE.



Project
Horton Heath Primary School

Drawing Title
Landscape and Public Realm
Planting Plan - Sheet 5

Date 18.05.2026 Scale 1:200 @A0 Drawn by LA Check by RM&W
Project No 332613072 Drawing No OHH-ZZ-00-DR-L-000205 Revision B

Stantec

Stantec UK Limited
101 Victoria Street
Bristol
BS1 4JY
T: 0117 929 9677

stantec.com/uk