




The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER ENGINEER'S AND LANDSCAPING DRAWINGS.
2. ALL DIMENSIONS ARE IN METRES UNLESS NOTED OTHERWISE.
3. DO NOT SCALE FROM THIS DRAWING.
4. ALL LEVELS ARE IN METRES ABOVE ORDNANCE DATUM (AOD)
5. THE USE OF THIS DRAWING DOES NOT ABSOLVE THE CLIENT FROM THEIR RESPONSIBILITIES IN REGARDS TO HEALTH & SAFETY AND CDM REGULATIONS.



FLOW CONTROL CHAMBER WITH HYDRO-BRAKE



This document is suitable only for the purpose noted above.
Use of this document for any other purpose is not permitted.



EASTLEIGH
BOROUGH COUNCIL

EASTLEIGH BOROUGH COUNCIL

Title

ONE HORTON HEATH PRIMARY SCHOOL
DRAINAGE CONSTRUCTION DETAILS

Project No. 332612639	A1 Scale AS SHOWN
Revision P01	Drawing No. OHH-STN-00-XX-DR-C-000504

Appendix F MicroDrainage Calculations Northern Network



Project Number: 332613072

Stantec UK Ltd		Page 1
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Northern Network

Pipe Sizes STANDARD Manhole Sizes STANDARD

FEH Rainfall Model	
Return Period (years)	2
FEH Rainfall Version	1999
Site Location GB 447800 117600 SU 47800 17600	
C (1km)	-0.028
D1 (1km)	0.423
D2 (1km)	0.310
D3 (1km)	0.398
E (1km)	0.304
F (1km)	2.288
Maximum Rainfall (mm/hr)	50
Maximum Time of Concentration (mins)	30
Foul Sewage (l/s/ha)	0.000
Volumetric Runoff Coeff.	0.840
PIMP (%)	100
Add Flow / Climate Change (%)	0
Minimum Backdrop Height (m)	0.200
Maximum Backdrop Height (m)	1.500
Min Design Depth for Optimisation (m)	1.200
Min Vel for Auto Design only (m/s)	1.00
Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Network Design Table for Northern Network

- Indicates pipe length does not match coordinates
« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	34.298	0.205	167.0	0.114	4.00	0.0	0.600	o	225	Pipe/Conduit	
1.001	14.041	0.084	167.0	0.040	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.002	22.191	0.133	167.0	0.034	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.003	18.722	0.079	237.0	0.064	0.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	4.57	26.125	0.114	0.0	0.0	0.0	1.01	40.1	17.3
1.001	50.00	4.80	25.920	0.154	0.0	0.0	0.0	1.01	40.1	23.4
1.002	50.00	5.17	25.836	0.188	0.0	0.0	0.0	1.01	40.1	28.5
1.003	50.00	5.47	25.628	0.252	0.0	0.0	0.0	1.02	71.9	38.2

Stantec UK Ltd

Caversham Bridge House

Waterman Place

Reading, RG1 8DN

Date 15/05/2026

File 332613072-STN-HDG-XX-MD...

Innovyze

One Horton Heath

Primary School

Northern Network

Designed by AB

Checked by JS

Network 2020.1.3

Page 2



Network Design Table for Northern Network

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.004	27.698	0.116	238.8	0.104	0.00	0.0	0.600	o	300	Pipe/Conduit	
1.005	35.735	0.150	238.0	0.096	0.00	0.0	0.600	o	300	Pipe/Conduit	
2.000	36.069	0.152	237.3	0.129	4.00	0.0	0.600	o	300	Pipe/Conduit	
2.001	36.209	0.152	238.2	0.115	0.00	0.0	0.600	o	450	Pipe/Conduit	
2.002	43.198	0.356	121.3	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
2.003	29.762	0.367	81.1	0.036	0.00	0.0	0.600	o	450	Pipe/Conduit	
1.006	26.412	0.069	382.8	0.028	0.00	0.0	0.600	o	450	Pipe/Conduit	
1.007	25.562	0.064	399.4	0.054	0.00	0.0	0.600	o	450	Pipe/Conduit	
1.008	5.083	0.013	391.0	0.031	0.00	0.0	0.600	o	450	Pipe/Conduit	
3.000	35.587	0.218	163.2	0.057	4.00	0.0	0.600	o	225	Pipe/Conduit	
3.001	4.962	0.060	82.7	0.035	0.00	0.0	0.600	o	225	Pipe/Conduit	
3.002	32.527	0.195	167.0	0.053	0.00	0.0	0.600	o	225	Pipe/Conduit	
3.003	11.969	0.050	239.4	0.030	0.00	0.0	0.600	o	300	Pipe/Conduit	
4.000	20.912	0.312	67.0	0.028	4.00	0.0	0.600	o	150	Pipe/Conduit	
4.001	33.085	0.291	113.7	0.032	0.00	0.0	0.600	o	225	Pipe/Conduit	
4.002	31.704	0.203	156.2	0.047	0.00	0.0	0.600	o	225	Pipe/Conduit	
4.003	7.178	0.238	30.2	0.058	0.00	0.0	0.600	o	225	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.004	48.39	5.93	25.549	0.356	0.0	0.0	0.0	1.01	71.6	52.3
1.005	45.74	6.51	25.433	0.452	0.0	0.0	0.0	1.01	71.7	62.7
2.000	50.00	4.59	26.310	0.129	0.0	0.0	0.0	1.02	71.8	19.6
2.001	50.00	5.05	26.008	0.244	0.0	0.0	0.0	1.31	208.8	37.0
2.002	50.00	5.44	25.856	0.244	0.0	0.0	0.0	1.84	293.4	37.0
2.003	49.73	5.66	25.500	0.280	0.0	0.0	0.0	2.26	359.3	42.2
1.006	44.04	6.94	25.133	0.760	0.0	0.0	0.0	1.03	164.3	101.5
1.007	42.52	7.36	25.064	0.814	0.0	0.0	0.0	1.01	160.8	105.0
1.008	42.24	7.44	25.000	0.845	0.0	0.0	0.0	1.02	162.5	108.3
3.000	50.00	4.58	25.941	0.057	0.0	0.0	0.0	1.02	40.6	8.6
3.001	50.00	4.64	25.723	0.092	0.0	0.0	0.0	1.44	57.2	14.0
3.002	50.00	5.18	25.663	0.145	0.0	0.0	0.0	1.01	40.1	22.0
3.003	50.00	5.37	25.393	0.175	0.0	0.0	0.0	1.01	71.5	26.5
4.000	50.00	4.28	26.537	0.028	0.0	0.0	0.0	1.23	21.7	4.2
4.001	50.00	4.73	26.150	0.060	0.0	0.0	0.0	1.23	48.7	9.1
4.002	50.00	5.24	25.859	0.107	0.0	0.0	0.0	1.04	41.5	16.2
4.003	50.00	5.29	25.656	0.165	0.0	0.0	0.0	2.39	95.1	25.0

©1982-2020 Innovyze

Stantec UK Ltd		Page 3
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Network Design Table for Northern Network

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
3.004	26.116	0.206	126.8	0.012	0.00	0.0	0.600	o	300	Pipe/Conduit	
1.009	13.444	0.784	17.1	0.068	0.00	0.0	0.600	o	450	Pipe/Conduit	
1.010	8.265	0.083	99.6	0.070	0.00	0.0	0.600	o	225	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
3.004	49.61	5.69	25.343	0.352	0.0	0.0	0.0	1.39	98.6	53.0
1.009	42.08	7.49	24.987	1.265	0.0	0.0	0.0	4.93	783.8	161.5
1.010	41.74	7.60	24.203	1.335	0.0	0.0	0.0	1.31	52.1«	169.0

Stantec UK Ltd		Page 4
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Manhole Schedules for Northern Network

MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Pipe Out Diameter (mm)	Pipes In PN	Pipes In Invert Level (m)	Pipes In Diameter (mm)	Backdrop (mm)
SW01	27.250	1.125	Open Manhole	1200	1.000	26.125	225				
SW02	27.359	1.440	Open Manhole	1200	1.001	25.920	225	1.000	25.920	225	
SW03	27.250	1.414	Open Manhole	1200	1.002	25.836	225	1.001	25.836	225	
SW04	27.265	1.637	Open Manhole	1200	1.003	25.628	300	1.002	25.703	225	
SW05	27.325	1.776	Open Manhole	1200	1.004	25.549	300	1.003	25.549	300	
SW06	27.224	1.791	Open Manhole	1200	1.005	25.433	300	1.004	25.433	300	
SW07	27.510	1.200	Open Manhole	1200	2.000	26.310	300				
SW08	27.649	1.641	Open Manhole	1350	2.001	26.008	450	2.000	26.158	300	
SW09	27.652	1.796	Open Manhole	1350	2.002	25.856	450	2.001	25.856	450	
SW10	26.754	1.254	Open Manhole	1350	2.003	25.500	450	2.002	25.500	450	
SW11	27.083	1.950	Open Manhole	1350	1.006	25.133	450	1.005	25.283	300	
								2.003	25.133	450	
SW12	27.026	1.962	Open Manhole	1350	1.007	25.064	450	1.006	25.064	450	
SW13	27.115	2.115	Open Manhole	1350	1.008	25.000	450	1.007	25.000	450	
SW14	27.366	1.425	Open Manhole	1200	3.000	25.941	225				
SW15	27.148	1.425	Open Manhole	1200	3.001	25.723	225	3.000	25.723	225	
SW16	27.088	1.425	Open Manhole	1200	3.002	25.663	225	3.001	25.663	225	
SW17	27.198	1.805	Open Manhole	1200	3.003	25.393	300	3.002	25.468	225	
SW18	27.887	1.350	Open Manhole	1200	4.000	26.537	150				
SW19	27.575	1.425	Open Manhole	1200	4.001	26.150	225	4.000	26.225	150	
SW20	27.284	1.425	Open Manhole	1200	4.002	25.859	225	4.001	25.859	225	
SW21	27.081	1.425	Open Manhole	1200	4.003	25.656	225	4.002	25.656	225	
SW22	27.167	1.824	Open Manhole	1200	3.004	25.343	300	3.003	25.343	300	
								4.003	25.418	225	
SW23	27.000	2.013	Open Manhole	1350	1.009	24.987	450	1.008	24.987	450	
								3.004	25.137	300	
SW24	26.650	2.447	Open Manhole	1350	1.010	24.203	225	1.009	24.203	450	
EX MH40	26.720	2.600	Open Manhole	1500		OUTFALL		1.010	24.120	225	

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
SW01	449070.813	116932.442	449070.813	116932.442	Required	
SW02	449097.511	116953.972	449097.511	116953.972	Required	

Stantec UK Ltd		Page 5
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Manhole Schedules for Northern Network

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
SW03	449088.669	116964.878	449088.669	116964.878	Required	
SW04	449105.920	116978.836	449105.920	116978.836	Required	
SW05	449123.484	116985.319	449123.484	116985.319	Required	
SW06	449144.817	117002.985	449144.817	117002.985	Required	
SW07	449093.819	116939.465	449093.819	116939.465	Required	
SW08	449121.791	116962.236	449121.791	116962.236	Required	
SW09	449149.872	116985.095	449149.872	116985.095	Required	
SW10	449152.089	117032.155	449152.089	117032.155	Required	
SW11	449122.359	117030.781	449122.359	117030.781	Required	
SW12	449101.929	117014.041	449101.929	117014.041	Required	
SW13	449082.180	116997.812	449082.180	116997.812	Required	
SW14	449062.711	116922.691	449062.711	116922.691	Required	
SW15	449040.425	116950.436	449040.425	116950.436	Required	
SW16	449040.966	116955.369	449040.966	116955.369	Required	
SW17	449066.127	116975.983	449066.127	116975.983	Required	

Caversham Bridge House
Waterman Place
Reading, RG1 8DN

One Horton Heath
Primary School
Northern Network



Date	15/05/2026
------	------------

Designed by AB

File 332613072-STN-HDG-XX-MD...

Checked by JS

Innovyze

Network 2020.1.3

Manhole Schedules for Northern Network

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
SW18	449034.268	116917.919	449034.268	116917.919	Required	
SW19	449018.850	116932.047	449018.850	116932.047	Required	
SW20	449026.932	116964.130	449026.932	116964.130	Required	
SW21	449051.558	116984.097	449051.558	116984.097	Required	
SW22	449058.632	116985.315	449058.632	116985.315	Required	
SW23	449078.942	117001.731	449078.942	117001.731	Required	
SW24	449070.211	117011.955	449070.211	117011.955	Required	
EX MH40	449062.266	117014.232			No Entry	

Stantec UK Ltd		Page 7
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

PIPELINE SCHEDULES for Northern Network

Upstream Manhole

- Indicates pipe length does not match coordinates

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	o	225	SW01	27.250	26.125	0.900	Open Manhole	1200
1.001	o	225	SW02	27.359	25.920	1.215	Open Manhole	1200
1.002	o	225	SW03	27.250	25.836	1.189	Open Manhole	1200
1.003	o	300	SW04	27.265	25.628	1.337	Open Manhole	1200
1.004	o	300	SW05	27.325	25.549	1.476	Open Manhole	1200
1.005	o	300	SW06	27.224	25.433	1.491	Open Manhole	1200
2.000	o	300	SW07	27.510	26.310	0.900	Open Manhole	1200
2.001	o	450	SW08	27.649	26.008	1.191	Open Manhole	1350
2.002	o	450	SW09	27.652	25.856	1.346	Open Manhole	1350
2.003	o	450	SW10	26.754	25.500	0.804	Open Manhole	1350
1.006	o	450	SW11	27.083	25.133	1.500	Open Manhole	1350
1.007	o	450	SW12	27.026	25.064	1.512	Open Manhole	1350
1.008	o	450	SW13	27.115	25.000	1.665	Open Manhole	1350
3.000	o	225	SW14	27.366	25.941	1.200	Open Manhole	1200
3.001	o	225	SW15	27.148	25.723	1.200	Open Manhole	1200
3.002	o	225	SW16	27.088	25.663	1.200	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	34.298	167.0	SW02	27.359	25.920	1.215	Open Manhole	1200
1.001	14.041	167.0	SW03	27.250	25.836	1.189	Open Manhole	1200
1.002	22.191	167.0	SW04	27.265	25.703	1.337	Open Manhole	1200
1.003	18.722	237.0	SW05	27.325	25.549	1.476	Open Manhole	1200
1.004	27.698	238.8	SW06	27.224	25.433	1.491	Open Manhole	1200
1.005	35.735	238.0	SW11	27.083	25.283	1.500	Open Manhole	1350
2.000	36.069	237.3	SW08	27.649	26.158	1.191	Open Manhole	1350
2.001	36.209	238.2	SW09	27.652	25.856	1.346	Open Manhole	1350
2.002	43.198#	121.3	SW10	26.754	25.500	0.804	Open Manhole	1350
2.003	29.762	81.1	SW11	27.083	25.133	1.500	Open Manhole	1350
1.006	26.412	382.8	SW12	27.026	25.064	1.512	Open Manhole	1350
1.007	25.562	399.4	SW13	27.115	25.000	1.665	Open Manhole	1350
1.008	5.083	391.0	SW23	27.000	24.987	1.563	Open Manhole	1350
3.000	35.587	163.2	SW15	27.148	25.723	1.200	Open Manhole	1200
3.001	4.962	82.7	SW16	27.088	25.663	1.200	Open Manhole	1200
3.002	32.527	167.0	SW17	27.198	25.468	1.505	Open Manhole	1200

Stantec UK Ltd		Page 8
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

PIPELINE SCHEDULES for Northern Network

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
3.003	o	300	SW17	27.198	25.393	1.505	Open Manhole	1200
4.000	o	150	SW18	27.887	26.537	1.200	Open Manhole	1200
4.001	o	225	SW19	27.575	26.150	1.200	Open Manhole	1200
4.002	o	225	SW20	27.284	25.859	1.200	Open Manhole	1200
4.003	o	225	SW21	27.081	25.656	1.200	Open Manhole	1200
3.004	o	300	SW22	27.167	25.343	1.524	Open Manhole	1200
1.009	o	450	SW23	27.000	24.987	1.563	Open Manhole	1350
1.010	o	225	SW24	26.650	24.203	2.222	Open Manhole	1350

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
3.003	11.969	239.4	SW22	27.167	25.343	1.524	Open Manhole	1200
4.000	20.912	67.0	SW19	27.575	26.225	1.200	Open Manhole	1200
4.001	33.085	113.7	SW20	27.284	25.859	1.200	Open Manhole	1200
4.002	31.704	156.2	SW21	27.081	25.656	1.200	Open Manhole	1200
4.003	7.178	30.2	SW22	27.167	25.418	1.524	Open Manhole	1200
3.004	26.116	126.8	SW23	27.000	25.137	1.563	Open Manhole	1350
1.009	13.444	17.1	SW24	26.650	24.203	1.997	Open Manhole	1350
1.010	8.265	99.6	EX MH40	26.720	24.120	2.375	Open Manhole	1500

Simulation Criteria for Northern Network

Volumetric Runoff Coeff	0.840	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	13
Number of Online Controls	2	Number of Time/Area Diagrams	1
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model FEH
Return Period (years) 2

Stantec UK Ltd		Page 9
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Synthetic Rainfall Details

FEH Rainfall Version	1999
Site Location GB 447800 117600 SU 47800 17600	
C (1km)	-0.028
D1 (1km)	0.423
D2 (1km)	0.310
D3 (1km)	0.398
E (1km)	0.304
F (1km)	2.288
Summer Storms	Yes
Winter Storms	No
Cv (Summer)	0.840
Cv (Winter)	0.840
Storm Duration (mins)	30

Stantec UK Ltd		Page 10
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Online Controls for Northern Network

Orifice Manhole: SW21, DS/PN: 4.003, Volume (m³): 2.8

Diameter (m) 0.100 Discharge Coefficient 0.600 Invert Level (m) 25.656

Hydro-Brake® Optimum Manhole: SW24, DS/PN: 1.010, Volume (m³): 5.4

Unit Reference	MD-SHE-0201-2540-2300-2540
Design Head (m)	2.300
Design Flow (l/s)	25.4
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	201
Invert Level (m)	24.203
Minimum Outlet Pipe Diameter (mm)	225
Suggested Manhole Diameter (mm)	1800

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	2.300	25.4
Flush-Flo™	0.670	25.4
Kick-Flo®	1.415	20.1
Mean Flow over Head Range	-	22.1

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	6.9	1.200	23.3	3.000	28.8	7.000	43.3
0.200	19.1	1.400	20.5	3.500	31.0	7.500	44.8
0.300	22.8	1.600	21.3	4.000	33.1	8.000	46.2
0.400	24.2	1.800	22.6	4.500	35.0	8.500	47.6
0.500	25.0	2.000	23.7	5.000	36.8	9.000	48.9
0.600	25.3	2.200	24.8	5.500	38.6	9.500	50.2
0.800	25.3	2.400	25.9	6.000	40.2		
1.000	24.6	2.600	26.9	6.500	41.8		

Stantec UK Ltd		Page 11
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Storage Structures for Northern Network

Porous Car Park Manhole: SW01, DS/PN: 1.000

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	22.0
Membrane Percolation (mm/hr)	1000	Length (m)	43.0
Max Percolation (l/s)	262.8	Slope (1:X)	0.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	26.650	Membrane Depth (mm)	0

Porous Car Park Manhole: SW04, DS/PN: 1.003

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	21.0
Membrane Percolation (mm/hr)	1000	Length (m)	29.0
Max Percolation (l/s)	169.2	Slope (1:X)	0.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	26.665	Membrane Depth (mm)	0

Porous Car Park Manhole: SW05, DS/PN: 1.004

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	13.0
Membrane Percolation (mm/hr)	1000	Length (m)	33.0
Max Percolation (l/s)	119.2	Slope (1:X)	0.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	26.725	Membrane Depth (mm)	0

Porous Car Park Manhole: SW06, DS/PN: 1.005

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	15.0
Membrane Percolation (mm/hr)	1000	Length (m)	35.0
Max Percolation (l/s)	145.8	Slope (1:X)	0.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	26.600	Membrane Depth (mm)	0

Tank or Pond Manhole: SW10, DS/PN: 2.003

Invert Level (m) 25.500

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	77.0	0.500	172.0	1.000	293.0

Porous Car Park Manhole: SW12, DS/PN: 1.007

Infiltration Coefficient Base (m/hr)	0.00000	Safety Factor	2.0
Membrane Percolation (mm/hr)	1000	Porosity	0.30
Max Percolation (l/s)	60.0	Invert Level (m)	26.400

Stantec UK Ltd		Page 12																		
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network																			
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS																			
Innovyze	Network 2020.1.3																			
<u>Porous Car Park Manhole: SW12, DS/PN: 1.007</u> Width (m) 8.0 Depression Storage (mm) 5 Length (m) 27.0 Evaporation (mm/day) 3 Slope (1:X) 0.0 Membrane Depth (mm) 0 <u>Cellular Storage Manhole: SW13, DS/PN: 1.008</u> Invert Level (m) 25.000 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>120.0</td><td>0.0</td><td>1.000</td><td>120.0</td><td>0.0</td></tr><tr><td>0.500</td><td>120.0</td><td>0.0</td><td>1.001</td><td>0.0</td><td>0.0</td></tr></table> <u>Porous Car Park Manhole: SW16, DS/PN: 3.002</u> Infiltration Coefficient Base (m/hr) 0.00000 Width (m) 10.0 Membrane Percolation (mm/hr) 1000 Length (m) 32.0 Max Percolation (l/s) 88.9 Slope (1:X) 0.0 Safety Factor 2.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 26.488 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: SW19, DS/PN: 4.001</u> Infiltration Coefficient Base (m/hr) 0.00000 Width (m) 10.0 Membrane Percolation (mm/hr) 1000 Length (m) 18.0 Max Percolation (l/s) 50.0 Slope (1:X) 0.0 Safety Factor 2.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 26.975 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: SW20, DS/PN: 4.002</u> Infiltration Coefficient Base (m/hr) 0.00000 Width (m) 10.0 Membrane Percolation (mm/hr) 1000 Length (m) 28.0 Max Percolation (l/s) 77.8 Slope (1:X) 0.0 Safety Factor 2.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 26.684 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: SW21, DS/PN: 4.003</u> Infiltration Coefficient Base (m/hr) 0.00000 Width (m) 10.0 Membrane Percolation (mm/hr) 1000 Length (m) 25.0 Max Percolation (l/s) 69.4 Slope (1:X) 0.0 Safety Factor 2.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 26.481 Membrane Depth (mm) 0			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	120.0	0.0	1.000	120.0	0.0	0.500	120.0	0.0	1.001	0.0	0.0
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)															
0.000	120.0	0.0	1.000	120.0	0.0															
0.500	120.0	0.0	1.001	0.0	0.0															
©1982-2020 Innovyze																				

Stantec UK Ltd		Page 13
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Porous Car Park Manhole: SW22, DS/PN: 3.004

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	6.0
Membrane Percolation (mm/hr)	1000	Length (m)	10.0
Max Percolation (l/s)	16.7	Slope (1:X)	0.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	26.567	Membrane Depth (mm)	0

Cellular Storage Manhole: SW24, DS/PN: 1.010

Invert Level (m)	24.206	Safety Factor	2.0
Infiltration Coefficient Base (m/hr)	0.00000	Porosity	0.95
Infiltration Coefficient Side (m/hr)	0.00000		

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	260.0	0.0	1.000	260.0	0.0
0.500	260.0	0.0	1.001	0.0	0.0

Time Area Diagram at Pipe Number 2.002 for Northern Network

Total Area (ha) 0.055

Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area
From:	To:	From:	To:	From:	To:	From:	To:
0	2 0.000	6	8 0.000	12	14 0.011	18	20 0.011
2	4 0.000	8	10 0.000	14	16 0.011		
4	6 0.000	10	12 0.011	16	18 0.011		

Stantec UK Ltd		Page 14
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Northern Network

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 13
 Number of Online Controls 2 Number of Time/Area Diagrams 1
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH
 FEH Rainfall Version 2013
 Site Location GB 447800 117600 SU 47800 17600
 Data Type Catchment
 Cv (Summer) 0.840
 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status OFF
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 0, 0, 40

									Water
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Level (m)
1.000	SW01	15 Summer	2	+0%	30/15 Summer				26.246
1.001	SW02	30 Summer	2	+0%	30/15 Summer				26.053
1.002	SW03	30 Summer	2	+0%	30/15 Summer				25.981
1.003	SW04	30 Summer	2	+0%	30/15 Summer				25.791
1.004	SW05	30 Summer	2	+0%	30/15 Summer				25.737
1.005	SW06	30 Summer	2	+0%	30/15 Summer				25.643
2.000	SW07	15 Summer	2	+0%	100/15 Summer				26.439
2.001	SW08	15 Summer	2	+0%					26.154
2.002	SW09	15 Summer	2	+0%	100/60 Summer				25.975
2.003	SW10	30 Summer	2	+0%	100/60 Summer				25.601
1.006	SW11	30 Summer	2	+0%	30/15 Summer				25.412
1.007	SW12	30 Summer	2	+0%	30/15 Summer				25.339
1.008	SW13	60 Summer	2	+0%	30/30 Summer				25.244
3.000	SW14	15 Summer	2	+0%	100/15 Summer				26.024
3.001	SW15	15 Summer	2	+0%	30/15 Summer				25.832
3.002	SW16	15 Summer	2	+0%	30/15 Summer				25.794

Stantec UK Ltd		Page 15
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Northern Network

PN	US/MH Name	Surcharged Flooded		Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)					
1.000	SW01	-0.104	0.000	0.42		5 15.8	OK	
1.001	SW02	-0.091	0.000	0.65		22.9	OK	
1.002	SW03	-0.080	0.000	0.73		26.6	OK	
1.003	SW04	-0.136	0.000	0.55	5	34.1	OK	
1.004	SW05	-0.111	0.000	0.70	5	45.3	OK	
1.005	SW06	-0.090	0.000	0.81	5	53.9	OK	
2.000	SW07	-0.171	0.000	0.38		25.4	OK	
2.001	SW08	-0.304	0.000	0.23		41.8	OK	
2.002	SW09	-0.331	0.000	0.16		40.8	OK	
2.003	SW10	-0.349	0.000	0.11		34.9	OK	
1.006	SW11	-0.171	0.000	0.64		88.7	OK	
1.007	SW12	-0.175	0.000	0.68	11	92.3	OK	
1.008	SW13	-0.206	0.000	0.57	23	65.7	OK	
3.000	SW14	-0.142	0.000	0.29		10.9	OK	
3.001	SW15	-0.116	0.000	0.46		16.0	OK	
3.002	SW16	-0.094	0.000	0.59	7	22.4	OK	

Stantec UK Ltd		Page 16
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Northern Network

									Water
	US/MH			Return	Climate	First (X)	First (Y)	First (Z)	Overflow
PN	Name	Storm		Period	Change	Surcharge	Flood	Overflow	Act.
3.003	SW17	15	Summer	2	+0%	100/15	Summer		25.538
4.000	SW18	15	Summer	2	+0%	30/15	Summer		26.590
4.001	SW19	15	Summer	2	+0%	30/15	Summer		26.222
4.002	SW20	30	Summer	2	+0%	2/15	Summer		26.190
4.003	SW21	30	Summer	2	+0%	2/15	Summer		26.168
3.004	SW22	30	Summer	2	+0%	100/15	Summer		25.483
1.009	SW23	60	Summer	2	+0%	100/15	Summer		25.117
1.010	SW24	240	Summer	2	+0%	2/30	Summer		24.661

US/MH		Surcharged Flooded		Half Drain		Pipe		Level	
PN	Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Status	Exceeded
3.003	SW17	-0.155	0.000	0.46			26.6	OK	
4.000	SW18	-0.097	0.000	0.27			5.5	OK	
4.001	SW19	-0.153	0.000	0.21		7	9.7	OK	
4.002	SW20	0.106	0.000	0.30		5	11.6	SURCHARGED	
4.003	SW21	0.287	0.000	0.21		10	14.2	SURCHARGED	
3.004	SW22	-0.160	0.000	0.45		10	39.4	OK	
1.009	SW23	-0.320	0.000	0.18			92.1	OK	
1.010	SW24	0.233	0.000	0.61		82	24.8	SURCHARGED	

Stantec UK Ltd		Page 17
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Northern Network

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 13
 Number of Online Controls 2 Number of Time/Area Diagrams 1
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH
 FEH Rainfall Version 2013
 Site Location GB 447800 117600 SU 47800 17600
 Data Type Catchment
 Cv (Summer) 0.840
 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status OFF
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 0, 0, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

									Water		
	US/MH			Return	Climate	First (X)		First (Y)	First (Z)	Overflow	Level
PN	Name	Storm	Period		Change	Surcharge		Flood	Overflow	Act.	(m)
1.000	SW01	30	Summer	30	+0%	30/15	Summer				26.658
1.001	SW02	15	Summer	30	+0%	30/15	Summer				26.636
1.002	SW03	30	Summer	30	+0%	30/15	Summer				26.561
1.003	SW04	15	Summer	30	+0%	30/15	Summer				26.389
1.004	SW05	15	Summer	30	+0%	30/15	Summer				26.308
1.005	SW06	30	Summer	30	+0%	30/15	Summer				26.095
2.000	SW07	15	Summer	30	+0%	100/15	Summer				26.515
2.001	SW08	15	Summer	30	+0%						26.246
2.002	SW09	15	Summer	30	+0%	100/60	Summer				26.045
2.003	SW10	30	Summer	30	+0%	100/60	Summer				25.695
1.006	SW11	30	Summer	30	+0%	30/15	Summer				25.653
1.007	SW12	30	Summer	30	+0%	30/15	Summer				25.546
1.008	SW13	60	Summer	30	+0%	30/30	Summer				25.453

Stantec UK Ltd		Page 18
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Northern Network

PN	US/MH Name	Surcharged		Flooded		Half Drain		Pipe	Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Flow (l/s)		
1.000	SW01	0.308	0.000	0.94			4	35.4	SURCHARGED	
1.001	SW02	0.491	0.000	1.16				40.5	SURCHARGED	
1.002	SW03	0.500	0.000	1.27				46.4	SURCHARGED	
1.003	SW04	0.462	0.000	0.96			7	59.9	SURCHARGED	
1.004	SW05	0.460	0.000	1.37			7	88.5	SURCHARGED	
1.005	SW06	0.362	0.000	1.71			10	113.0	SURCHARGED	
2.000	SW07	-0.095	0.000	0.79				52.1	OK	
2.001	SW08	-0.212	0.000	0.52				95.8	OK	
2.002	SW09	-0.261	0.000	0.36				95.8	OK	
2.003	SW10	-0.255	0.000	0.21				63.6	OK	
1.006	SW11	0.070	0.000	1.24				172.3	SURCHARGED	
1.007	SW12	0.032	0.000	1.34			18	181.2	SURCHARGED	
1.008	SW13	0.003	0.000	1.32			42	151.8	SURCHARGED	

Stantec UK Ltd		Page 19
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Northern Network

									Water
	US/MH			Return	Climate	First (X)	First (Y)	First (Z)	Overflow
PN	Name	Storm	Period	Change		Surcharge	Flood	Overflow	Act.
3.000	SW14	15	Summer	30	+0%	100/15	Summer		
3.001	SW15	15	Summer	30	+0%	30/15	Summer		
3.002	SW16	15	Summer	30	+0%	30/15	Summer		
3.003	SW17	15	Summer	30	+0%	100/15	Summer		
4.000	SW18	15	Summer	30	+0%	30/15	Summer		
4.001	SW19	15	Summer	30	+0%	30/15	Summer		
4.002	SW20	15	Summer	30	+0%	2/15	Summer		
4.003	SW21	30	Summer	30	+0%	2/15	Summer		
3.004	SW22	15	Summer	30	+0%	100/15	Summer		
1.009	SW23	120	Summer	30	+0%	100/15	Summer		
1.010	SW24	120	Summer	30	+0%	2/30	Summer		

US/MH		Surcharged Flooded		Half Drain		Pipe		Level	
PN	Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Status	Exceeded
3.000	SW14	-0.006	0.000	0.56			21.6	OK	
3.001	SW15	0.156	0.000	0.91			31.3	SURCHARGED	
3.002	SW16	0.135	0.000	1.28		3	48.2	SURCHARGED	
3.003	SW17	-0.053	0.000	0.99			57.3	OK	
4.000	SW18	0.108	0.000	0.52			10.7	SURCHARGED	
4.001	SW19	0.362	0.000	0.41		13	18.6	SURCHARGED	
4.002	SW20	0.600	0.000	0.82		15	31.8	SURCHARGED	
4.003	SW21	0.703	0.000	0.28		11	19.6	SURCHARGED	
3.004	SW22	-0.076	0.000	0.90		6	79.8	OK	
1.009	SW23	-0.074	0.000	0.32			161.2	OK	
1.010	SW24	0.925	0.000	0.63			25.4	SURCHARGED	

Stantec UK Ltd		Page 20
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Northern Network

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 13
 Number of Online Controls 2 Number of Time/Area Diagrams 1
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH
 FEH Rainfall Version 2013
 Site Location GB 447800 117600 SU 47800 17600
 Data Type Catchment
 Cv (Summer) 0.840
 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status OFF
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 0, 0, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

US/MH		Storm	Return Climate		First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name		Period	Change	Surcharge	Flood	Overflow	Act.	Level (m)
1.000	SW01	30 Summer	100	+40%	30/15 Summer				26.752
1.001	SW02	15 Summer	100	+40%	30/15 Summer				26.925
1.002	SW03	15 Summer	100	+40%	30/15 Summer				26.900
1.003	SW04	15 Summer	100	+40%	30/15 Summer				26.715
1.004	SW05	15 Summer	100	+40%	30/15 Summer				26.701
1.005	SW06	15 Summer	100	+40%	30/15 Summer				26.507
2.000	SW07	15 Summer	100	+40%	100/15 Summer				26.745
2.001	SW08	120 Winter	100	+40%					26.458
2.002	SW09	120 Winter	100	+40%	100/60 Summer				26.453
2.003	SW10	120 Winter	100	+40%	100/60 Summer				26.451
1.006	SW11	120 Winter	100	+40%	30/15 Summer				26.453
1.007	SW12	120 Winter	100	+40%	30/15 Summer				26.451
1.008	SW13	120 Winter	100	+40%	30/30 Summer				26.461

Stantec UK Ltd		Page 21
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Northern Network

PN	US/MH Name	Surcharged		Flooded		Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow	Overflow					
1.000	SW01	0.402	0.000	1.19			9	45.1	SURCHARGED	
1.001	SW02	0.780	0.000	1.43				50.1	SURCHARGED	
1.002	SW03	0.839	0.000	1.37				50.2	SURCHARGED	
1.003	SW04	0.787	0.000	0.97			5	60.5	SURCHARGED	
1.004	SW05	0.852	0.000	1.37			10	88.7	SURCHARGED	
1.005	SW06	0.774	0.000	2.25			14	148.5	SURCHARGED	
2.000	SW07	0.135	0.000	1.35				89.2	SURCHARGED	
2.001	SW08	0.000	0.000	0.26				47.0	OK	
2.002	SW09	0.147	0.000	0.21				54.9	SURCHARGED	
2.003	SW10	0.501	0.000	0.18				56.9	SURCHARGED	
1.006	SW11	0.870	0.000	1.02				141.4	SURCHARGED	
1.007	SW12	0.937	0.000	1.11				149.9	SURCHARGED	
1.008	SW13	1.011	0.000	1.34				153.9	SURCHARGED	

Stantec UK Ltd		Page 22
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Northern Network

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
3.000	SW14	15 Summer	100	+40%	100/15 Summer				26.888
3.001	SW15	15 Summer	100	+40%	30/15 Summer				26.668
3.002	SW16	15 Summer	100	+40%	30/15 Summer				26.510
3.003	SW17	120 Winter	100	+40%	100/15 Summer				26.481
4.000	SW18	15 Summer	100	+40%	30/15 Summer				27.192
4.001	SW19	15 Summer	100	+40%	30/15 Summer				26.944
4.002	SW20	30 Summer	100	+40%	2/15 Summer				26.786
4.003	SW21	60 Summer	100	+40%	2/15 Summer				26.740
3.004	SW22	120 Winter	100	+40%	100/15 Summer				26.478
1.009	SW23	120 Winter	100	+40%	100/15 Summer				26.464
1.010	SW24	120 Winter	100	+40%	2/30 Summer				26.461

PN	US/MH Name	Depth (m)	Surcharged Volume (m³)	Flooded Flow / Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
3.000	SW14	0.722	0.000	0.92		35.1	SURCHARGED	
3.001	SW15	0.720	0.000	1.63		56.1	SURCHARGED	
3.002	SW16	0.622	0.000	1.88		3 70.9	SURCHARGED	
3.003	SW17	0.788	0.000	0.58		33.7	SURCHARGED	
4.000	SW18	0.505	0.000	0.88		18.0	SURCHARGED	
4.001	SW19	0.569	0.000	0.83		38.0	SURCHARGED	
4.002	SW20	0.702	0.000	0.87	27	33.7	SURCHARGED	
4.003	SW21	0.859	0.000	0.31	15	21.1	SURCHARGED	
3.004	SW22	0.835	0.000	0.62	39	55.2	SURCHARGED	
1.009	SW23	1.027	0.000	0.41		203.7	SURCHARGED	
1.010	SW24	2.033	0.000	0.63		25.4	FLOOD RISK	

Stantec UK Ltd		Page 23
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network +45%CC	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Northern Network

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	13
Number of Online Controls	2	Number of Time/Area Diagrams	1
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 447800 117600 SU 47800 17600
Data Type	Catchment
Cv (Summer)	0.840
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	100
Climate Change (%)	45

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	SW01	30 Summer	100	+45%	100/15 Summer				26.759
1.001	SW02	15 Summer	100	+45%	100/15 Summer				26.911
1.002	SW03	15 Summer	100	+45%	100/15 Summer				26.898
1.003	SW04	15 Summer	100	+45%	100/15 Summer				26.722
1.004	SW05	15 Summer	100	+45%	100/15 Summer				26.708
1.005	SW06	120 Winter	100	+45%	100/15 Summer				26.519
2.000	SW07	15 Summer	100	+45%	100/15 Summer				26.767
2.001	SW08	120 Winter	100	+45%	100/120 Summer				26.507
2.002	SW09	120 Winter	100	+45%	100/60 Summer				26.506
2.003	SW10	120 Winter	100	+45%	100/30 Summer				26.504
1.006	SW11	120 Winter	100	+45%	100/15 Summer				26.505
1.007	SW12	120 Winter	100	+45%	100/15 Summer				26.502
1.008	SW13	120 Winter	100	+45%	100/15 Summer				26.513

Stantec UK Ltd		Page 24
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Northern Network +45%CC	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Northern Network

PN	US/MH Name	Surcharged		Flooded		Half Drain		Pipe		Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)				
1.000	SW01	0.409	0.000	1.19			9 44.8			SURCHARGED	
1.001	SW02	0.767	0.000	1.44			50.4			SURCHARGED	
1.002	SW03	0.837	0.000	1.38			50.5			SURCHARGED	
1.003	SW04	0.795	0.000	0.99		5	61.4			SURCHARGED	
1.004	SW05	0.859	0.000	1.39		10	90.0			SURCHARGED	
1.005	SW06	0.786	0.000	1.27			84.3			SURCHARGED	
2.000	SW07	0.157	0.000	1.39			92.3			SURCHARGED	
2.001	SW08	0.049	0.000	0.27			48.7			SURCHARGED	
2.002	SW09	0.200	0.000	0.22			56.8			SURCHARGED	
2.003	SW10	0.554	0.000	0.19			57.7			FLOOD RISK	
1.006	SW11	0.922	0.000	1.04			144.9			SURCHARGED	
1.007	SW12	0.988	0.000	1.14		37	153.6			SURCHARGED	
1.008	SW13	1.063	0.000	1.36			156.5			SURCHARGED	

Appendix G MicroDrainage Calculations Southern Network



Stantec UK Ltd		Page 1
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Southern Network

Pipe Sizes STANDARD Manhole Sizes STANDARD

FEH Rainfall Model	
Return Period (years)	2
FEH Rainfall Version	1999
Site Location GB 447800 117600 SU 47800 17600	
C (1km)	-0.028
D1 (1km)	0.423
D2 (1km)	0.310
D3 (1km)	0.398
E (1km)	0.304
F (1km)	2.288
Maximum Rainfall (mm/hr)	50
Maximum Time of Concentration (mins)	30
Foul Sewage (l/s/ha)	0.000
Volumetric Runoff Coeff.	0.840
PIMP (%)	100
Add Flow / Climate Change (%)	0
Minimum Backdrop Height (m)	0.200
Maximum Backdrop Height (m)	1.500
Min Design Depth for Optimisation (m)	1.200
Min Vel for Auto Design only (m/s)	1.00
Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Network Design Table for Southern Network

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	48.206	0.289	167.0	0.000	4.00	0.0	0.600	o	225	Pipe/Conduit	
S1.001	48.206	0.203	237.5	0.052	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.002	42.597	0.192	221.9	0.074	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.003	10.249	0.570	18.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
S2.000	55.556	0.556	99.9	0.088	4.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	50.00	4.80	26.875	0.000	0.0	0.0	0.0	1.01	40.1	0.0
S1.001	50.00	5.59	26.511	0.052	0.0	0.0	0.0	1.02	71.8	7.9
S1.002	46.83	6.26	26.308	0.126	0.0	0.0	0.0	1.05	74.3	17.9
S1.003	46.62	6.31	26.116	0.126	0.0	0.0	0.0	3.73	263.3	17.9
S2.000	50.00	4.92	26.575	0.088	0.0	0.0	0.0	1.01	17.8	13.3

Stantec UK Ltd		Page 2
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Network Design Table for Southern Network

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S2.001	25.397	0.227	111.9	0.037	0.00	0.0	0.600	o	225	Pipe/Conduit	
S3.000	44.176	0.442	99.9	0.054	4.00	0.0	0.600	o	150	Pipe/Conduit	
S3.001	16.785	0.168	99.9	0.034	0.00	0.0	0.600	o	225	Pipe/Conduit	
S3.002	17.177	0.267	64.3	0.025	0.00	0.0	0.600	o	225	Pipe/Conduit	
S2.002	20.345	0.096	211.9	0.033	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.004	12.524	0.496	25.3	0.051	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.005	15.022	0.063	238.4	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S2.001	50.00	5.26	25.944	0.125	0.0	0.0	0.0	1.24	49.1	19.0
S3.000	50.00	4.73	26.669	0.054	0.0	0.0	0.0	1.01	17.8	8.2
S3.001	50.00	4.95	26.152	0.088	0.0	0.0	0.0	1.31	52.0	13.3
S3.002	50.00	5.12	25.984	0.113	0.0	0.0	0.0	1.63	64.9	17.1
S2.002	50.00	5.58	25.642	0.271	0.0	0.0	0.0	1.08	76.1	41.1
S1.004	46.33	6.37	25.546	0.448	0.0	0.0	0.0	3.14	222.1	63.0
S1.005	45.30	6.62	25.050	0.448	0.0	0.0	0.0	1.01	71.7	63.0

Stantec UK Ltd		Page 3
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Manhole Schedules for Southern Network

MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdr (mm)
SSW01	28.000	1.125	Open Manhole	1200	S1.000	26.875	225				
SSW02	28.220	1.709	Open Manhole	1200	S1.001	26.511	300	S1.000	26.586	225	
SSW03	28.346	2.037	Open Manhole	1200	S1.002	26.308	300	S1.001	26.308	300	
SSW04	28.235	2.119	Open Manhole	1200	S1.003	26.116	300	S1.002	26.116	300	
SSW05	27.925	1.350	Open Manhole	1200	S2.000	26.575	150				
SSW06	28.180	2.236	Open Manhole	1200	S2.001	25.944	225	S2.000	26.019	150	
SSW07	28.019	1.350	Open Manhole	1200	S3.000	26.669	150				
SSW08	28.601	2.449	Open Manhole	1200	S3.001	26.152	225	S3.000	26.227	150	
SSW09	28.460	2.476	Open Manhole	1200	S3.002	25.984	225	S3.001	25.984	225	
SSW10	28.202	2.560	Open Manhole	1200	S2.002	25.642	300	S2.001	25.717	225	
								S3.002	25.717	225	
SSW11	28.075	2.529	Open Manhole	1200	S1.004	25.546	300	S1.003	25.546	300	
								S2.002	25.546	300	
SEX MH25	28.000	2.950	Open Manhole	1200	S1.005	25.050	300	S1.004	25.050	300	
S	28.000	3.013	Open Manhole	0		OUTFALL		S1.005	24.987	300	

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
SSW01	449129.681	116824.219	449129.681	116824.219	Required	
SSW02	449082.199	116832.546	449082.199	116832.546	Required	
SSW03	449034.718	116840.874	449034.718	116840.874	Required	
SSW04	449042.065	116882.832	449042.065	116882.832	Required	
SSW05	448968.621	116814.997	448968.621	116814.997	Required	
SSW06	448990.629	116866.009	448990.629	116866.009	Required	
SSW07	448986.064	116807.465	448986.064	116807.465	Required	

Stantec UK Ltd		Page 5
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

PIPELINE SCHEDULES for Southern Network

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	o	225	SSW01	28.000	26.875	0.900	Open Manhole	1200
S1.001	o	300	SSW02	28.220	26.511	1.409	Open Manhole	1200
S1.002	o	300	SSW03	28.346	26.308	1.737	Open Manhole	1200
S1.003	o	300	SSW04	28.235	26.116	1.819	Open Manhole	1200
S2.000	o	150	SSW05	27.925	26.575	1.200	Open Manhole	1200
S2.001	o	225	SSW06	28.180	25.944	2.011	Open Manhole	1200
S3.000	o	150	SSW07	28.019	26.669	1.200	Open Manhole	1200
S3.001	o	225	SSW08	28.601	26.152	2.224	Open Manhole	1200
S3.002	o	225	SSW09	28.460	25.984	2.251	Open Manhole	1200
S2.002	o	300	SSW10	28.202	25.642	2.260	Open Manhole	1200
S1.004	o	300	SSW11	28.075	25.546	2.229	Open Manhole	1200
S1.005	o	300	SEX MH25	28.000	25.050	2.650	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	48.206	167.0	SSW02	28.220	26.586	1.409	Open Manhole	1200
S1.001	48.206	237.5	SSW03	28.346	26.308	1.737	Open Manhole	1200
S1.002	42.597	221.9	SSW04	28.235	26.116	1.819	Open Manhole	1200
S1.003	10.249	18.0	SSW11	28.075	25.546	2.229	Open Manhole	1200
S2.000	55.556	99.9	SSW06	28.180	26.019	2.011	Open Manhole	1200
S2.001	25.397	111.9	SSW10	28.202	25.717	2.260	Open Manhole	1200
S3.000	44.176	99.9	SSW08	28.601	26.227	2.224	Open Manhole	1200
S3.001	16.785	99.9	SSW09	28.460	25.984	2.251	Open Manhole	1200
S3.002	17.177	64.3	SSW10	28.202	25.717	2.260	Open Manhole	1200
S2.002	20.345	211.9	SSW11	28.075	25.546	2.229	Open Manhole	1200
S1.004	12.524	25.3	SEX MH25	28.000	25.050	2.650	Open Manhole	1200
S1.005	15.022	238.4	S	28.000	24.987	2.713	Open Manhole	0

Stantec UK Ltd		Page 6
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Simulation Criteria for Southern Network

Volumetric Runoff Coeff	0.840	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	7
Number of Online Controls	2	Number of Time/Area Diagrams	3
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
Return Period (years)	2
FEH Rainfall Version	1999
Site Location	GB 447800 117600 SU 47800 17600
C (1km)	-0.028
D1 (1km)	0.423
D2 (1km)	0.310
D3 (1km)	0.398
E (1km)	0.304
F (1km)	2.288
Summer Storms	Yes
Winter Storms	No
Cv (Summer)	0.840
Cv (Winter)	0.840
Storm Duration (mins)	30

Stantec UK Ltd		Page 7
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

Online Controls for Southern Network

Orifice Manhole: SSW10, DS/PN: S2.002, Volume (m³): 4.5

Diameter (m) 0.100 Discharge Coefficient 0.600 Invert Level (m) 25.717

Hydro-Brake® Optimum Manhole: SEX MH25, DS/PN: S1.005, Volume (m³): 4.1

Unit Reference	MD-SHE-0148-1500-2800-1500
Design Head (m)	2.800
Design Flow (l/s)	15.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	148
Invert Level (m)	25.050
Minimum Outlet Pipe Diameter (mm)	225
Suggested Manhole Diameter (mm)	1500

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	2.800	15.0
Flush-Flo™	0.646	13.4
Kick-Flo®	1.328	10.5
Mean Flow over Head Range	-	12.3

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	5.3	1.200	11.8	3.000	15.5	7.000	23.2
0.200	10.8	1.400	10.8	3.500	16.7	7.500	24.0
0.300	12.1	1.600	11.5	4.000	17.8	8.000	24.8
0.400	12.9	1.800	12.2	4.500	18.8	8.500	25.5
0.500	13.2	2.000	12.8	5.000	19.8	9.000	26.2
0.600	13.4	2.200	13.4	5.500	20.7	9.500	26.9
0.800	13.3	2.400	13.9	6.000	21.6		
1.000	12.8	2.600	14.5	6.500	22.4		

Stantec UK Ltd		Page 8
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	
<u>Storage Structures for Southern Network</u>		
<u>Porous Car Park Manhole: SSW05, DS/PN: S2.000</u>		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m) 10.0
Membrane Percolation (mm/hr)	1000	Length (m) 46.0
Max Percolation (l/s)	127.8	Slope (1:X) 0.0
Safety Factor	2.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	27.325	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: SSW06, DS/PN: S2.001</u>		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m) 10.0
Membrane Percolation (mm/hr)	1000	Length (m) 17.6
Max Percolation (l/s)	48.9	Slope (1:X) 0.0
Safety Factor	2.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	27.580	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: SSW07, DS/PN: S3.000</u>		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m) 10.0
Membrane Percolation (mm/hr)	1000	Length (m) 13.2
Max Percolation (l/s)	36.7	Slope (1:X) 0.0
Safety Factor	2.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	27.419	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: SSW08, DS/PN: S3.001</u>		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m) 10.0
Membrane Percolation (mm/hr)	1000	Length (m) 13.6
Max Percolation (l/s)	37.8	Slope (1:X) 0.0
Safety Factor	2.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	28.000	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: SSW09, DS/PN: S3.002</u>		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m) 10.0
Membrane Percolation (mm/hr)	1000	Length (m) 11.0
Max Percolation (l/s)	30.6	Slope (1:X) 0.0
Safety Factor	2.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	27.860	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: SSW10, DS/PN: S2.002</u>		
Infiltration Coefficient Base (m/hr)	0.00000	Max Percolation (l/s) 32.8
Membrane Percolation (mm/hr)	1000	Safety Factor 2.0
©1982-2020 Innovyze		

Stantec UK Ltd		Page 9																																																																																																																																																																								
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network																																																																																																																																																																									
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS																																																																																																																																																																									
Innovyze	Network 2020.1.3																																																																																																																																																																									
<u>Porous Car Park Manhole: SSW10, DS/PN: S2.002</u> <table><tr><td>Porosity</td><td>0.30</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Invert Level (m)</td><td>27.602</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Width (m)</td><td>10.0</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Length (m)</td><td>11.8</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Cellular Storage Manhole: SSW11, DS/PN: S1.004</u> <table><tr><td>Invert Level (m)</td><td>25.546</td><td>Safety Factor</td><td>2.0</td></tr><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Porosity</td><td>0.95</td></tr><tr><td>Infiltration Coefficient Side (m/hr)</td><td>0.00000</td><td></td><td></td></tr></table> <table><tr><td>Depth (m)</td><td>Area (m²)</td><td>Inf. Area (m²)</td><td>Depth (m)</td><td>Area (m²)</td><td>Inf. Area (m²)</td></tr><tr><td>0.000</td><td>180.0</td><td>0.0</td><td>1.000</td><td>180.0</td><td>0.0</td></tr><tr><td>0.500</td><td>180.0</td><td>0.0</td><td>1.001</td><td>0.0</td><td>0.0</td></tr></table> <u>Time Area Diagram at Pipe Number S1.000 for Southern Network</u> Total Area (ha) 0.095 <table><tr><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td></tr><tr><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td></tr><tr><td>0 2 0.000</td><td></td><td>6 8 0.000</td><td></td><td>12 14 0.019</td><td></td><td>18 20 0.019</td><td></td></tr><tr><td>2 4 0.000</td><td></td><td>8 10 0.000</td><td></td><td>14 16 0.019</td><td></td><td></td><td></td></tr><tr><td>4 6 0.000</td><td></td><td>10 12 0.019</td><td></td><td>16 18 0.019</td><td></td><td></td><td></td></tr></table> <u>Time Area Diagram at Pipe Number S1.001 for Southern Network</u> Total Area (ha) 0.100 <table><tr><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td></tr><tr><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td></tr><tr><td>0 2 0.000</td><td></td><td>6 8 0.000</td><td></td><td>12 14 0.020</td><td></td><td>18 20 0.020</td><td></td></tr><tr><td>2 4 0.000</td><td></td><td>8 10 0.000</td><td></td><td>14 16 0.020</td><td></td><td></td><td></td></tr><tr><td>4 6 0.000</td><td></td><td>10 12 0.020</td><td></td><td>16 18 0.020</td><td></td><td></td><td></td></tr></table> <u>Time Area Diagram at Pipe Number S1.002 for Southern Network</u> Total Area (ha) 0.110 <table><tr><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td><td>Time (mins)</td><td>Area</td></tr><tr><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td><td>From: To: (ha)</td><td></td></tr><tr><td>0 2 0.000</td><td></td><td>6 8 0.000</td><td></td><td>12 14 0.022</td><td></td><td>18 20 0.022</td><td></td></tr><tr><td>2 4 0.000</td><td></td><td>8 10 0.000</td><td></td><td>14 16 0.022</td><td></td><td></td><td></td></tr><tr><td>4 6 0.000</td><td></td><td>10 12 0.022</td><td></td><td>16 18 0.022</td><td></td><td></td><td></td></tr></table>			Porosity	0.30	Slope (1:X)	0.0	Invert Level (m)	27.602	Depression Storage (mm)	5	Width (m)	10.0	Evaporation (mm/day)	3	Length (m)	11.8	Membrane Depth (mm)	0	Invert Level (m)	25.546	Safety Factor	2.0	Infiltration Coefficient Base (m/hr)	0.00000	Porosity	0.95	Infiltration Coefficient Side (m/hr)	0.00000			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	180.0	0.0	1.000	180.0	0.0	0.500	180.0	0.0	1.001	0.0	0.0	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	From: To: (ha)		From: To: (ha)		From: To: (ha)		From: To: (ha)		0 2 0.000		6 8 0.000		12 14 0.019		18 20 0.019		2 4 0.000		8 10 0.000		14 16 0.019				4 6 0.000		10 12 0.019		16 18 0.019				Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	From: To: (ha)		From: To: (ha)		From: To: (ha)		From: To: (ha)		0 2 0.000		6 8 0.000		12 14 0.020		18 20 0.020		2 4 0.000		8 10 0.000		14 16 0.020				4 6 0.000		10 12 0.020		16 18 0.020				Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	From: To: (ha)		From: To: (ha)		From: To: (ha)		From: To: (ha)		0 2 0.000		6 8 0.000		12 14 0.022		18 20 0.022		2 4 0.000		8 10 0.000		14 16 0.022				4 6 0.000		10 12 0.022		16 18 0.022				©1982-2020 Innovyze	
Porosity	0.30	Slope (1:X)	0.0																																																																																																																																																																							
Invert Level (m)	27.602	Depression Storage (mm)	5																																																																																																																																																																							
Width (m)	10.0	Evaporation (mm/day)	3																																																																																																																																																																							
Length (m)	11.8	Membrane Depth (mm)	0																																																																																																																																																																							
Invert Level (m)	25.546	Safety Factor	2.0																																																																																																																																																																							
Infiltration Coefficient Base (m/hr)	0.00000	Porosity	0.95																																																																																																																																																																							
Infiltration Coefficient Side (m/hr)	0.00000																																																																																																																																																																									
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																																																																																																																					
0.000	180.0	0.0	1.000	180.0	0.0																																																																																																																																																																					
0.500	180.0	0.0	1.001	0.0	0.0																																																																																																																																																																					
Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area																																																																																																																																																																			
From: To: (ha)		From: To: (ha)		From: To: (ha)		From: To: (ha)																																																																																																																																																																				
0 2 0.000		6 8 0.000		12 14 0.019		18 20 0.019																																																																																																																																																																				
2 4 0.000		8 10 0.000		14 16 0.019																																																																																																																																																																						
4 6 0.000		10 12 0.019		16 18 0.019																																																																																																																																																																						
Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area																																																																																																																																																																			
From: To: (ha)		From: To: (ha)		From: To: (ha)		From: To: (ha)																																																																																																																																																																				
0 2 0.000		6 8 0.000		12 14 0.020		18 20 0.020																																																																																																																																																																				
2 4 0.000		8 10 0.000		14 16 0.020																																																																																																																																																																						
4 6 0.000		10 12 0.020		16 18 0.020																																																																																																																																																																						
Time (mins)	Area	Time (mins)	Area	Time (mins)	Area	Time (mins)	Area																																																																																																																																																																			
From: To: (ha)		From: To: (ha)		From: To: (ha)		From: To: (ha)																																																																																																																																																																				
0 2 0.000		6 8 0.000		12 14 0.022		18 20 0.022																																																																																																																																																																				
2 4 0.000		8 10 0.000		14 16 0.022																																																																																																																																																																						
4 6 0.000		10 12 0.022		16 18 0.022																																																																																																																																																																						

Stantec UK Ltd		Page 10
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Southern Network

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 7
 Number of Online Controls 2 Number of Time/Area Diagrams 3
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH
 FEH Rainfall Version 2013
 Site Location GB 447800 117600 SU 47800 17600
 Data Type Catchment
 Cv (Summer) 0.840
 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status OFF
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	SSW01	30 Summer	2	+0%	100/15 Summer			
S1.001	SSW02	30 Summer	2	+0%	100/15 Summer			
S1.002	SSW03	30 Summer	2	+0%	100/15 Summer			
S1.003	SSW04	30 Summer	2	+0%	100/30 Summer			
S2.000	SSW05	30 Summer	2	+0%	2/30 Summer			
S2.001	SSW06	30 Summer	2	+0%	2/15 Summer			
S3.000	SSW07	15 Summer	2	+0%	30/15 Summer			
S3.001	SSW08	30 Summer	2	+0%	2/15 Summer			
S3.002	SSW09	30 Summer	2	+0%	2/15 Summer			
S2.002	SSW10	30 Summer	2	+0%	2/15 Summer			
S1.004	SSW11	120 Summer	2	+0%	30/15 Summer			
S1.005	SEX MH25	120 Summer	2	+0%	2/15 Summer			

Stantec UK Ltd		Page 11
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Southern Network

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
S1.000	SSW01	26.957	-0.143	0.000	0.28		10.9	OK
S1.001	SSW02	26.630	-0.181	0.000	0.33		22.2	OK
S1.002	SSW03	26.459	-0.150	0.000	0.50		34.4	OK
S1.003	SSW04	26.202	-0.214	0.000	0.18		34.4	OK
S2.000	SSW05	26.738	0.013	0.000	0.82	4	14.3	SURCHARGED
S2.001	SSW06	26.696	0.527	0.000	0.25	9	11.1	SURCHARGED
S3.000	SSW07	26.754	-0.065	0.000	0.61	4	10.6	OK
S3.001	SSW08	26.705	0.328	0.000	0.28	7	12.9	SURCHARGED
S3.002	SSW09	26.693	0.484	0.000	0.23	11	13.1	SURCHARGED
S2.002	SSW10	26.677	0.735	0.000	0.30	16	19.8	SURCHARGED
S1.004	SSW11	25.788	-0.058	0.000	0.10	49	17.5	OK
S1.005	SEX MH25	25.778	0.428	0.000	0.22		13.3	SURCHARGED

PN	US/MH Name	Level Exceeded
S1.000	SSW01	
S1.001	SSW02	
S1.002	SSW03	
S1.003	SSW04	
S2.000	SSW05	
S2.001	SSW06	
S3.000	SSW07	
S3.001	SSW08	
S3.002	SSW09	
S2.002	SSW10	
S1.004	SSW11	
S1.005	SEX MH25	

Stantec UK Ltd		Page 12
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Southern Network

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	7
Number of Online Controls	2	Number of Time/Area Diagrams	3
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 447800 117600 SU 47800 17600
Data Type	Catchment
Cv (Summer)	0.840
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	SSW01	30 Summer	30	+0%	100/15 Summer			
S1.001	SSW02	30 Summer	30	+0%	100/15 Summer			
S1.002	SSW03	30 Summer	30	+0%	100/15 Summer			
S1.003	SSW04	30 Summer	30	+0%	100/30 Summer			
S2.000	SSW05	60 Summer	30	+0%	2/30 Summer			
S2.001	SSW06	30 Summer	30	+0%	2/15 Summer			
S3.000	SSW07	30 Summer	30	+0%	30/15 Summer			
S3.001	SSW08	15 Summer	30	+0%	2/15 Summer			
S3.002	SSW09	15 Summer	30	+0%	2/15 Summer			
S2.002	SSW10	15 Summer	30	+0%	2/15 Summer			
S1.004	SSW11	60 Winter	30	+0%	30/15 Summer			
S1.005	SEX MH25	60 Winter	30	+0%	2/15 Summer			

Stantec UK Ltd		Page 13
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Southern Network

PN	US/MH Name	Water	Surcharged	Flooded	Half Drain		Pipe	Status	
		Level (m)	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)		Flow (l/s)
S1.000	SSW01	27.002	-0.098	0.000	0.61			23.3	OK
S1.001	SSW02	26.699	-0.113	0.000	0.70			47.4	OK
S1.002	SSW03	26.604	-0.004	0.000	1.00			69.3	OK
S1.003	SSW04	26.242	-0.175	0.000	0.37			69.3	OK
S2.000	SSW05	27.391	0.666	0.000	0.77		15	13.3	SURCHARGED
S2.001	SSW06	27.587	1.418	0.000	0.36		28	16.3	SURCHARGED
S3.000	SSW07	27.518	0.699	0.000	0.66		9	11.4	SURCHARGED
S3.001	SSW08	27.658	1.281	0.000	0.45		18	20.9	SURCHARGED
S3.002	SSW09	27.642	1.433	0.000	0.26		20	15.1	SURCHARGED
S2.002	SSW10	27.602	1.660	0.000	0.42		27	28.0	SURCHARGED
S1.004	SSW11	26.212	0.366	0.000	0.11			19.2	SURCHARGED
S1.005	SEX MH25	26.224	0.874	0.000	0.22			13.3	SURCHARGED

PN	US/MH Name	Level Exceeded
S1.000	SSW01	
S1.001	SSW02	
S1.002	SSW03	
S1.003	SSW04	
S2.000	SSW05	
S2.001	SSW06	
S3.000	SSW07	
S3.001	SSW08	
S3.002	SSW09	
S2.002	SSW10	
S1.004	SSW11	
S1.005	SEX MH25	

Stantec UK Ltd		Page 14
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Southern Network

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	7
Number of Online Controls	2	Number of Time/Area Diagrams	3
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 447800 117600 SU 47800 17600
Data Type	Catchment
Cv (Summer)	0.840
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	SSW01	120 Winter	100	+40%	100/15 Summer			
S1.001	SSW02	120 Winter	100	+40%	100/15 Summer			
S1.002	SSW03	120 Winter	100	+40%	100/15 Summer			
S1.003	SSW04	120 Winter	100	+40%	100/30 Summer			
S2.000	SSW05	60 Summer	100	+40%	2/30 Summer			
S2.001	SSW06	30 Summer	100	+40%	2/15 Summer			
S3.000	SSW07	60 Summer	100	+40%	30/15 Summer			
S3.001	SSW08	15 Summer	100	+40%	2/15 Summer			
S3.002	SSW09	15 Summer	100	+40%	2/15 Summer			
S2.002	SSW10	15 Summer	100	+40%	2/15 Summer			
S1.004	SSW11	120 Winter	100	+40%	30/15 Summer			
S1.005	SEX MH25	120 Winter	100	+40%	2/15 Summer			

Stantec UK Ltd		Page 15
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Southern Network

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status
S1.000	SSW01	27.721	0.621	0.000	0.47		17.9	FLOOD RISK
S1.001	SSW02	27.705	0.894	0.000	0.54		36.7	SURCHARGED
S1.002	SSW03	27.690	1.082	0.000	0.83		57.2	SURCHARGED
S1.003	SSW04	27.668	1.251	0.000	0.29		55.6	SURCHARGED
S2.000	SSW05	27.578	0.853	0.000	0.58	66	10.0	SURCHARGED
S2.001	SSW06	27.673	1.504	0.000	0.31	9	14.2	SURCHARGED
S3.000	SSW07	27.764	0.945	0.000	0.60	26	10.4	FLOOD RISK
S3.001	SSW08	27.869	1.492	0.000	0.40	46	18.3	SURCHARGED
S3.002	SSW09	27.797	1.588	0.000	0.64	47	36.8	SURCHARGED
S2.002	SSW10	27.686	1.744	0.000	0.44	10	28.9	SURCHARGED
S1.004	SSW11	27.657	1.811	0.000	0.11		19.9	SURCHARGED
S1.005	SEX MH25	27.645	2.295	0.000	0.24		14.5	SURCHARGED

PN	US/MH Name	Level Exceeded
S1.000	SSW01	
S1.001	SSW02	
S1.002	SSW03	
S1.003	SSW04	
S2.000	SSW05	
S2.001	SSW06	
S3.000	SSW07	
S3.001	SSW08	
S3.002	SSW09	
S2.002	SSW10	
S1.004	SSW11	
S1.005	SEX MH25	

Stantec UK Ltd		Page 16
Caversham Bridge House Waterman Place Reading, RG1 8DN	One Horton Heath Primary School Southern Network +45%CC	
Date 15/05/2026 File 332613072-STN-HDG-XX-MD...	Designed by AB Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Southern Network

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	7
Number of Online Controls	2	Number of Time/Area Diagrams	3
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 447800 117600 SU 47800 17600
Data Type	Catchment
Cv (Summer)	0.840
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	100
Climate Change (%)	45

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.
S1.000	SSW01	120 Winter	100	+45%	100/15 Summer			
S1.001	SSW02	120 Winter	100	+45%	100/15 Summer			
S1.002	SSW03	120 Winter	100	+45%	100/15 Summer			
S1.003	SSW04	120 Winter	100	+45%	100/30 Summer			
S2.000	SSW05	120 Winter	100	+45%	100/15 Summer			
S2.001	SSW06	30 Summer	100	+45%	100/15 Summer			
S3.000	SSW07	60 Summer	100	+45%	100/15 Summer			
S3.001	SSW08	15 Summer	100	+45%	100/15 Summer			
S3.002	SSW09	15 Summer	100	+45%	100/15 Summer			
S2.002	SSW10	30 Summer	100	+45%	100/15 Summer			
S1.004	SSW11	120 Winter	100	+45%	100/15 Summer			
S1.005	SEX MH25	120 Winter	100	+45%	100/15 Summer			

Stantec UK Ltd		Page 17
Caversham Bridge House	One Horton Heath	
Waterman Place	Primary School	
Reading, RG1 8DN	Southern Network +45%CC	
Date 15/05/2026	Designed by AB	
File 332613072-STN-HDG-XX-MD...	Checked by JS	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Southern Network

PN	US/MH Name	Water	Surcharged	Flooded			Half Drain	Pipe	Status
		Level (m)	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	
S1.000	SSW01	27.825	0.725	0.000	0.48			18.5	FLOOD RISK
S1.001	SSW02	27.806	0.995	0.000	0.56			38.0	SURCHARGED
S1.002	SSW03	27.787	1.179	0.000	0.85			59.3	SURCHARGED
S1.003	SSW04	27.759	1.343	0.000	0.30			56.5	SURCHARGED
S2.000	SSW05	27.606	0.881	0.000	0.60		51	10.3	SURCHARGED
S2.001	SSW06	27.683	1.514	0.000	0.30		11	13.7	SURCHARGED
S3.000	SSW07	27.782	0.963	0.000	0.56		43	9.7	FLOOD RISK
S3.001	SSW08	27.885	1.508	0.000	0.40		48	18.7	SURCHARGED
S3.002	SSW09	27.813	1.604	0.000	0.66		50	38.4	SURCHARGED
S2.002	SSW10	27.695	1.753	0.000	0.43		16	28.5	SURCHARGED
S1.004	SSW11	27.746	1.900	0.000	0.11			19.9	SURCHARGED
S1.005	SEX MH25	27.734	2.384	0.000	0.24			14.7	FLOOD RISK

PN	US/MH Name	Level Exceeded
S1.000	SSW01	
S1.001	SSW02	
S1.002	SSW03	
S1.003	SSW04	
S2.000	SSW05	
S2.001	SSW06	
S3.000	SSW07	
S3.001	SSW08	
S3.002	SSW09	
S2.002	SSW10	
S1.004	SSW11	
S1.005	SEX MH25	