

KTML Survey data sheet.

Site: 12, Malcolm Road, Chandlers Ford SO53 5BG													Surveyor: Sarah Kiss, Kiss Tree Management Limited		Survey date: 16/04/26		
Client		Ben Johnston - owner				Age class: S=sapling, Y=first 1/4 of life expectancy, EMa=Early Mature - second quarter of life expectancy, Ma=Mature - third 1/4 of life expectancy, LMa=Late Mature 4/4 of life expectancy, V=Veteran - displaying characteristics of very old age - beyond usual for species.											
Reference: proposed extension to existing property											Condition key: D= Dead or unstable, P=poor, F=Fair, G=Good, E=Excellent						
Tree no	Species	Ht (m)	Dia mms (@1.5)	RPA radius in m*	Crown Spread N, E, S, W				Canopy Ht	Age Class	Retention class - see key	Remaining life contribution	Physiological condition	Structural condition	Preliminary Management Recommendations		
T1	Oak (measured at 1.3m agl due to form)	14	1050	12.60	7	7	7.5	7	6	LaMa	A1, 3	40+	Good. Regrowth has good extension.	Good. Three stems from 1.3m above ground level with good unions and fairly even sized scaffolds (560, 480, 450mm dia). Historically reduced to south to reduce overhang.	None. Retain and protect through the proposal		
T2	Beech	21	980	11.76	8	8	8	8	4.5	Ma	A1,2,3	40+	Good, Viewed in spring while leaves still flushing but appeared normal for species.	Good to fair. Twin stem form 1.5m, slight inclusion at fork but no indication of movement or cracking. Rooting curtailed by presence of a boundary wall (now removed)	None. Retain and protect through the proposal		
T3	Beech	19		0.00	4.5	4.5	4.5	4.5	4.5	Ma	B2,3	20-40	Good.	Fair. Multistem from very near ground level. 4 main scaffolds arise from base. No indication of movement or splitting at unions.	None. Retain and protect through the proposal		
Note: The root protection zone suggested by BS5837 is twelve times the stem diameter measured radially from the centre of the stem. The RPA is capped at 15.0m.																	
Note: Minor deadwood is taken as less than 50mm in diameter. Major deadwood is taken as 50mm or more in diameter.																	
* Denotes a multiple stem tree where the stem diameter is measured at just above root flare and multiplied by 10 to achieve RPA																	