

ESTIMATE

46 Grange Park Mobile Homes
Hedge End
Southampton
SO30 2FP

Date: 26/02/2024

Description of Works

Specification to be carried out at above addresses.

- Front garden is 40 square metres

- Back Patio is 41 square metres

Excavating front and back of property

Remove all rubble

Supply and install MOT hardcore subbase

Area to be levelled and compacted to solid base

Supply and install weed control membrane

Supply and install drainage crate to the depth of 1 metre by 900 to take surface water front and back

Supply and install loose 20mm gravel to front and back of property

Driveway services if need be can be accessed 24 hours

Clean and tidy at all times

Total cost £7500.00 inc. VAT

NO DEPOSIT REQUIRED - PAYMENT UPON COMPLETION & SATISFACTION OF WORKS

Sub Total £

Grand Total £

Thank You For Your Business

14 Day Cool-Off Period



Find us on

Facebook

myBuilder.com



FORMPAVE LANDSCAPES & DRIVES LTD
12 Elm Grove, Runcton, Chichester, PO20 1PW

Company Registered Number 12298691