


Species Name	Girth	Height	Density	Specification	No.
<i>Carpinus betulus</i>		200-250cm	0.5Ct Double Staggered at 0.4m offset	Feathered 2x RB	842
<i>Carpinus betulus 'lucas'</i>	10-12cm	350-400cm	Counted	Heavy Standard Clear Stem min. 200 RB	2
<i>Aemulanchier x grandiflora 'Robin Hill'</i>	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem min. 200 RB 5 brks. 3x RB	3
<i>Sorbus aucuparia 'Chantrelle'</i>	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem min. 200 RB	4
<i>Corylus av. Majestic</i>	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem min. 200 RB 5 brks 3x RB	3
<i>Pyrus calleryana 'Chanticleer'</i>	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem min. 200 RB 5 brks 3x RB	3
<i>Acer campestre 'Elsrijk'</i>	18-20cm	450-500cm	Counted	Extra Heavy Standard Clear Stem min. 200 RB	6
<i>Betula utilis 'aquaticum'</i>	18-20cm	450-500cm	Counted	Extra Heavy Standard Clear Stem min. 200 RB	3
<i>Betula pendula</i>	18-20cm	450-500cm	Counted	Extra Heavy Standard Clear Stem min. 200 RB	3
<i>Acer campestre</i>	18-20cm	450-500cm	Counted	Extra Heavy Standard Clear Stem min. 200 RB	3
<i>Corylus colurna</i>	20-25cm	500-600cm	Counted	Semi-Mature Clear Stem min. 200 : 3x/4x RB	15

Species Name	Height	Pot Size	Specification	Density	No.
Amelanchier lamarckii	175-200cm	43"	Multistem C	Counted	2
Cornus sanguinea	30-40cm	5-7.5L	Bushy C	4"	155
Cornus sanguinea 'Midwinter Fire'	30-40cm	5-7.5L	Bushy C	4"	23
Escallonia 'Iveyi'	60-80cm	3L	Bushy 4 brks. C	0.5Cr Double Staggered at 0.4m offset	327
Eunonymus fortunei 'Dart's Blanket'	30-40cm	3L	Bushy 3 brks C	4"	267
Eunonymus fortunei 'Emerald Gaiety'	30-40cm	3L	Bushy 3 brks C	4"	136
Hebe 'Midsummer Beauty'	30-40cm	3L	Bushy C	0.5Cr	387
Hebe abicans 'Red Edge'	30-40cm	3L	Bushy C	0.5Cr	387
Hebe brachyophylla 'White Gem'	30-40cm	3L	Bushy C	0.5Cr	279
Hydrangea macrophylla 'Zebra'	30-40cm	3L	Bushy C	0.5Cr	304
Lonicera xylosteum	60-80cm	3L	Bushy 4 brks. C	0.5Cr Double Staggered at 0.4m offset	304
Osmanthus burkwoodii	30-40cm	3L	Bushy 4 brks. C	0.5Cr Double Staggered at 0.4m offset	513
Pachysandra terminalis	15-20cm	3L	Bushy C	0.5Cr	46
Skimmia confusa 'Kew Green'	30-40cm	3L	Bushy C	0.5Cr	323
Skimmia japonica 'Rubella'	30-40cm	3L	Bushy C	0.5Cr	44
Viburnum davidii	40-60cm	5-7.5L	Bushy C	0.5Cr	82
Viburnum opulus	60-80cm	5-7.5L	Bushy C	0.5Cr	82
Viburnum tinus	40-60cm	5-7.5L	Bushy C	0.5Cr	169

Climbers				
Species Name	Height	Pot Size	Specification	Density No.
Hydrangea petiolaris	80-100cm	10L	Several Shoots :Framed	Counted 4-
Lonicera japonica 'Hall's Prolific'	80-100cm	10L	Several Shoots :Framed	Counted 7-
Lonicera periclymenum 'Harlequin'	80-100cm	5-7.5L	Several Shoots :Framed	Counted 10-

Species Name	Height	Pot Size	Specification	Density	No.
<i>Deschampsia cespitosa</i>		3L	Full Pot	0.5Ctr	393
<i>Geranium 'Johnson Blue'</i>		3L	Full Pot	0.5Ctr	384
<i>Geranium renardi 'Brookside'</i>		3L	Full Pot	0.5Ctr	366
<i>Heuchera micrantha 'Palace Purple'</i>		3L	Full Pot	0.5Ctr	156
<i>Persicaria affinis 'Danceing Lady'</i>		5-7.5L	Full Pot	0.5Ctr	142
<i>Red sea hellebore 'Brilliant'</i>		5-7.5L	Full Pot	0.5Ctr	142
<i>Stipa tenuissima</i>		5-7.5L	Full Pot	0.5Ctr	212
<i>Verbena bonariensis</i>		5-7.5L	Full Pot	0.5Ctr	99

Native Hedgerow Species		Standard-B	Density	Percentage Contribution
Number	Mix	Specification		
60	Acer campestre	Standard-B	0.4C/D Double Staggered at 0.3m offset	5%
60	Crataegus betulus	Transplant	0.4C/D Double Staggered at 0.3m offset	5%
60	Calluna vulgaris	Transplant	0.4C/D Double Staggered at 0.3m offset	5%
60	Conocarpus perfoliatus	Standard-B	0.4C/D Double Staggered at 0.3m offset	5%
60	Prunus avium	Feathered	0.4C/D Double Staggered at 0.3m offset	10%
60	Prunus spinosa	Branched	0.4C/D Double Staggered at 0.3m offset	5%
60	Rosa canina	Branched	0.4C/D Double Staggered at 0.3m offset	5%
60	Sambucus nigra	Bushy	0.4C/D Double Staggered at 0.3m offset	10%
60	Viburnum lantana	Bushy	0.4C/D Double Staggered at 0.3m offset	0%
Total: 400 -				



NOTES:
DO NOT SCALE FROM DRAWING
NOT FOR CONSTRUCTION, FOR PLANNING
PURPOSES ONLY

- | Legend | |
|---|--|
|  | Existing trees to be retained and protected during construction |
|  | Proposed tree planting within soft landscape.
See detail on sheet 1 |
|  | Proposed tree planting within hard landscape.
See detail on sheet 1 |
|  | Proposed formal hedge planting to be planted in a double staggered row 300mm apart and at 400mm centres in each row. To be maintained at 1m height, 3 strand galvanised wire and tanalised softwood timber post fence, to BS1722-2:2020 Fencing. |
|  | Proposed mixed native hedge planting to be planted in a double staggered row 300mm apart and at 400mm centres in each row. To be maintained at 1m height and 1.5m height adjacent to site boundaries, 3 strand galvanised wire and tanalised softwood timber post fence, to BS1722-2:2020 Fencing. |
|  | Proposed shrub planting to receive 75mm bark mulch after planting operations |
|  | Proposed native mix shrub planting to be planted in groups of 5-7no. of each species and as above |
|  | Proposed meadow grassland to be seeded with EM2 Mixture as supplied by Emorsgate and sown at 4 grams per m ² , or similar and approved. |
|  | Proposed meadow grassland to be seeded with EW1 Woodland Mixture as supplied by Emorsgate and sown at 4 grams per m ² , or similar and approved. |
|  | Proposed grass areas to receive good quality anhrilly grass turves laid in line with good horticultural practices |
|  | Proposed Sub to be seeded with EM8 seed mix as supplied by Emorsgate Seeds and sown at 4 grams per m ² , or similar and approved |
|  | Proposed self-binding grass through open space and natural green areas (Breedon Golden Amber, or similar and approved), edging shall be steel 'Everedge' or similar and approved. |
|  | Proposed 400mm wide 75mm depth bark mulch strip over weed proof membrane to abut planting adjacent to sides or ends of parking bays |
|  | Proposed timber bench & bin RBA& J2822 from Prologic or similar and approved. |
|  | Cut lines - See sheet location plan on sheet 4 |
| Services | |
|  | Proposed position of Storm Water Sewer & Inspection Chamber. See drainage engineer design for details. |
|  | Proposed position of Foul Sewer & Inspection Chamber. See drainage engineer design for details. |
|  | Proposed position of Underground Attenuation Tank. See drainage engineers design for details. |
|  | Proposed position of Foul Drain. See drainage engineers design for details. |
|  | Proposed position of Street Lighting Column. See lighting engineers design for details. |

[illegible]

HEAD OFFICE
Rodbourn Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

4 & 5 The Old Mill, Fry's Yard, Bridge Street,
Godalming, GU7 1HP
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close,
Eastleigh, SO50 9SX
Tel: 02382 026300

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

Vistry Homes

scheme: Boorley Green Gatewa
Winchester Road, Botley

client: Vistry Homes

drawing: Landscape Proposals

date: May 2022

scale: 1:200@A1

rawing no: VYH23647 11 Sheet 2

drawn: RH/RK checked: DKM

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted: 2011. Copyright of this plan remains with ACD until all fees have been paid in full.