



TREE PLANTING

Two trees indicated on the Landscape Plan to be **BETULA PENDULA ALBA (BIRCH)**. Eventual Height & Spread; 25m / 10m. 8-10cm Girth, Height 1.5/2m (Bare-root) planted between March-May using 2 tree stakes 1-1.2m out of the ground with crossbeam & tree strapping used to tie in the trees. Trees to be mulched with pro grow after planting.

HEDGE PLANTING

CARPINUS BETULAS (HORNBEAM) Planted bare-root at no higher than 800-1m tall, 1 plant per/m planted along inside inner side of boundary fence, planted between March-May. Hedging to be mulched with pro grow after planting.

CELLULAR GRAVEL FILLED GRIDS

GRASS

LOW LEVEL PLANTING

Low Level Planting to be used to front of house. **LAVANDULA ANGUSTIFOLIA (Lavander)** – Known for attracting bees & butterflies with its fragrant flowers. **CORAL BELLS (Heuchera)** – Provides year-round interest with its foliage, beneficial to pollinators. 2 – 5L size pot plants. Plant selection to be based on site conditions. Planting should be done during spring (April-May) Plant according to the depth & spacing guidelines recommended on the plant label or pot. Plants to be mulched with pro grow after planting.

SUBJECT TO
BUILDING
REGULATIONS
APPROVAL

REVISION	DESCRIPTION	DATE
PROJECT	WEST END COTTAGE, SWAYTHLING ROAD, SOUTHAMPTON SO18 3HT	
CLIENT	ALAN PHILLIPS	
DRAWING	SITE PLAN PROPOSED SITE PLAN	
NO.	1776/B/54 C	
DATE	February 2025	
SCALE	1:100 at A1	
DRAWN BY:	MHU	CHECKED BY: LW