



REFUSE STRATEGY:

Private Refuse Storage for houses is located in rear gardens and moved by residents on collection day, to kerbside (on cartilage) or collection points.

Private Refuse Collection is from kerbside, adjacent to the dwelling boundary or from collection points.

Communal Refuse Storage is provided for apartments.

- Private refuse storage locations, generally in rear gardens. Moved on collection day by resident.
- Kerbside refuse collection points for individual houses.

Travel Distances

- Operatives - Generally 3-5m (25m max.)
- Residents - Generally <30m

Refuse Provision for Houses

- One 240 ltr. Wheeled Bin (Refuse)
- One 240 ltr. Wheeled Bin (Recycling)
- One 25 ltr. Kitchen Bin (Not Shown)

Refuse Collection Strategy

The storage and collection of refuse and materials associated with recycling has been carefully considered in the design of the scheme. The site layout has been designed to ensure that refuse and recycling collections can be undertaken from the adoptable and public road network at the front of properties.

The private streets have been designed to accommodate refuse vehicles and to ensure that the necessary standards relating to turning areas and roadways construction have been met. So as not to visually or physically detract from the appearance of the development, it is proposed that all dwelling houses will be provided with the necessary space to store their wheeled bins in rear gardens, with appropriate alleyways provided to enable bins to be brought to the fronts of properties for refuse collection area (BCP) on the day of collection.

Refuse collection points are situated such that refuse collection vehicles are not expected to reverse more than 15 metres. Also, where the refuse collection vehicle is unable to achieve direct access for waste collection a maximum distance of 20 metres for the transporting of waste to the refuse collection vehicle will not be exceeded.

The on plot storage capacity is fundamental in ensuring that residents have sufficient space to undertake segregation at the point of waste production. As such, an appropriate quantum of internal storage capacity will be provided within the kitchen of every dwelling.

Strategy for Flats

Occupants of the flats are to carry their refuse to an enclosed refuse store located within the building. All occupants will have access to the refuse store through the week.

Two strategies will be employed for houses

House refuse collection strategy 1: Houses that are to share a refuse collection point will have a designated area (BCP) from which the refuse service providers will collect refuse from. Occupants of these houses are to store their bins in their own private amenity space, moving their bins to the designated collection point on the day of collection only, and returning it to their property afterwards.

House refuse collection strategy 2: Houses that are to have their bins collected from the front of their property will store their bins in the rear garden and move them to the road side at the front of their property on collection days and return them to the rear garden once emptied.

Access for the refuse collection vehicles has been carefully planned and the necessary junctions have been tracked so that a refuse vehicle can enter and exit safely and the turning areas are also design to accommodate the manoeuvring arrangement for refuse vehicles.

As part of the handover packs for all new owners there will be information provided on the approved waste collection strategy for their property which they must adhere to, including contact details of the council's refuse department.

F	Tree locations amended in line with ACD planting proposals.	DGP	20.03.25
E	Tree locations amended in line with ACD planting proposals.	DGP	17.03.25
D	Updated for plot 132	DGP	05.02.25
C	Layout amended as per planner's comments.	DGP	16.12.24
B	Layout amended as per planner's comments.	DGP	03.10.24
A	Plot handing's reference added. Window added to side elevation. Window position updated to side elevation. Rear openings updated in line with plans.	ACG	26.04.24
Rev.	Description	Drawn	Date

miller homes

Miller Homes (Southern) Ltd
Unit 3,
Faraday Business Park,
Rankine Road
Basingstoke, RG24 8QB

Telephone 0870 336 4200
Fax 01256 708356
www.millerhomes.co.uk

Project Title

**Land to the North West of
Boorley Green, Hedge End**

Drawing Title

**Phase 1H & 1i
Refuse Plan**

Scale	Drawn By	Checked By	Authorised By
1:500			
	Date 08.04.24	Date	Date
Job No.	Drawing No.		Revision
817072	PH1H_1I_REFUSE_PLAN		F
Original Sheet Size A0			