



Prüfinstitut für
Abwassertechnik
GmbH

PERFORMANCE RESULTS

Otto Graf GmbH

Carl-Zeiss-Str. 2 – 6, 79331 Teningen, Germany

EN 12566-3

Small wastewater treatment systems for up to 50 PT

Small wastewater treatment system one2clean

SBR plant in one two-zone polypropylene tank

Nominal organic daily load*	0.27	kg/d		
Nominal hydraulic daily load	0.75	m ³ /d		
Material	polypropylene			
Treatment efficiency (nominal sequences)		Efficiency	Effluent	
	COD	94.2 %	43 mg/l	
	BOD ₅	98.0 %	7 mg/l	
	SS	96.3 %	14 mg/l	
	NH ₄ -N**	98.3 %	0.5 mg/l	
	N _{tot} **	87.0 %	7.9 mg/l	
Electrical consumption	0.63	kWh/d		
<i>*at a test influent of ≥ 300 mg/l BOD₅ (mean)</i>				
<i>**determined for temperatures ≥ 12°C in the bioreactor</i>				

Performance tested by:

PIA – Prüfinstitut für Abwassertechnik GmbH

(PIA GmbH)

Hergenrather Weg 30

52074 Aachen, Germany

This document replaces neither the declaration
of conformity nor the CE marking.



Notified Body
No.: 1739



Certified according to
ISO 9001:2008



Deutsche
Akkreditierungsstelle
D-PL-17712-01-00

Prüfinstitut für Abwassertechnik GmbH

geprüft - tested - testé

Elmar Lancé

May 2014